

# Schedule of lifts for Tower Crane A practical guidance







## Contents:

1.	<u>Introduction</u>	2
2.	Acronyms used through the document	2
3.	Requirements of a schedule	3
4.	<u>Lift classifications</u>	3
5.	<u>Lifting information alerts</u>	3
6.	Notes on accessories	4
7.	Ratings charts	4
8.	<u>Communications</u>	6
9.	Wind Assessment	. 11
10.	General safe considerations	. 12

#### Please note:

This document has been provided by Sir Robert McAlpine Limited. It has been checked to the best of our ability but may contain unintentional errors. As per BS 7121-1:2016, CDM 2015 and LOLER, it is the user's responsibility to verify that they understand and have made their own checks before using this document.

The user shall ensure that they properly risk assess and plan their own lifting operations to discharge their legal requirements.

No liability will be accepted for any incidents that result of those using this document.



## 1. Introduction:

This document has been produced to not only assist and provide guidance on industry accepted methodologies for tower crane lifting operations but also to provide a simple benchmark template that is easy to complete, containing all required information for a schedule of lifts.

All weights & dimensions in the schedules are representative only of standard/common measures throughout the industry and are shown in *red italicized text*. Where specific lifts exceed any of these then simply adjust gross weights, WLL of accessories and considered mode factors as necessary to perform the lifting operation in a safe manner.

The document follows the LEEA convention of 1000kg is equivalent to 1 tonne and the unit used is 't'. Where weights are < 1 t then the unit used will be kg.

Where underscores are used instead of numeric symbols i.e., \_t or \_mm then these are to be completed locally as the variation in the dimensions and weights [net or gross] are too great to cover generically in this document.

Please be aware that this document is not intended to replace appropriate planning of lifting operations by an appointed person. All lifting operations must be planned and managed by a competent person. The document is only to be used by people who have the appropriate training and competence for lift planning operations

Additionally, sector specific working restrictions have not been considered, e.g. exceptional hazard sites (nuclear, petrochemical etc.), working adjacent to railways etc.

The weight and geometry of loads has not been assessed in relation to any maximum safe wind speeds for the lifting operation (i.e. any sail effects on the loads).

# 2. Acronyms used through the document:

- FOS Factor of Safety
- SWL Safe Working Load
- WLL Working Load Limit
- wcs Worst [worse] Case Scenario
- [ru] Rounded up
- t Tonne
- kg Kilogram[s]
- c/w Complete with
- Min. Minimum
- EWL Effective Working Length
- DABs Daily activity briefings


- [l] Length
- [h] Height
- [w] Width
- [d] Diameter
- Inc. Including or inclusive of
- no. Number
- mm Millimetre
- m Metre
- RoTE Report of thorough examination
- @ at /of
- POWRA Point of work risk assessment

Process Owner: Head of Lifting
Approved By: C. Hook
Page: Page 2 of 118

Document No.: XXXX\_XXXXX Document Rev: 01



## 3. Requirements of a Schedule:



#### 4. Lift classifications:

The lift classifications stated throughout the document are based on all lifts being performed in full view of the crane operator with known weights, and for the simplest of lifting arrangements used.

The planning appointed person should assess each lift and classify accordingly to suit local lifting operation parameters.

Please note:

Lifting operations that are basic can be undertaken once the slinger-signaller has been briefed on the contents of the lift plan and has signed up to it. Intermediate lifting operations should only commence when the lifting supervisor is present until confident of the slinger-signaller's ability and the uniformity of the load being lifted. Complex lifting operations will require the Lifting Supervisor to be present at point of lift to monitor the lifting operation with the appointed person present on the project to brief the lifting operation to be performed.

Refer to: *BS 7121 – 1: 2016 4.3.2* for guidance

## 5. Notes on accessories:

It is assumed that Grade 10 8.4 t 4 leg chain slings with an EWL of 6m will be used as standard on the tower crane and therefore have been referenced throughout the lifting arrangements.

Where accessories are identified in the schedule 'as per design use', it is assumed that suitable FOS's have been designed into the accessory and as such need no further mode factors employed for that accessory.

When choosing accessories ensure that after mode factors have been used, the accessory is not used past 90% utilisation for the weight of load to be lifted. This produces a 10% safety margin which the user may choose to increase

All accessory lengths given are so that the accessory is used within an 'excluded' angle of 0-45 Deg.[off the  $\beta$ ]

Process Owner: Head of Lifting Document No.: XXXX\_XXXX\_XXXX Approved By: C. Hook Document Rev: 01

Page: Page 3 of 118 Date Approved: Dec 2024



# 6. Ratings charts:

# Flatwoven/ Endless round slings

Ratings for single and multi-leg use of flat woven slings and endless round slings within 90 Deg. *Please note:* 

SWL for 'Choker' hitch mode factors in each configuration given are shown in reduced by the required 0.8 factor.

	Flatwoven					
Straight lift with direct attachment	2 slings Direct attachment	2 slings Choked	3 or 4 slings with Direct attachment	3 or 4 slings Choked		
	OO" Max	8	20 Man			
	Е	ndless (round)				
1 t	1.4 t	1.12 t	2.1 t	1.68 t		
2 t	2.8 t	2.24 t	4.2 t	3.36 t		
3 <i>t</i>	4.2 t	3.36 t	6.3 t	5.04 t		
4 t	5.6 t	4.48 t	8.4 t	6.72 t		
5 t	7 t	5.6 t	10.5 t	8.4 t		
6 t	8.4 t	6.72 t	12.6 t	10.08 t		
8 t	11.2 t	8.96 t	16.8 t	13.44 t		
10 t	14 t	11.2 t	21 t	16.8 t		

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 4 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01 Dec 2024



# **Grade 8 chain slings**

Ratings for single and multi-leg chain slings within 60 Deg. Grade 8 chains slings *Please note:* 

SWL for 'Choker' hitch mode factors in each configuration given are shown in by the required 0.8 factor



and have been reduced

Chain sling details and configuration chart						
Chain Diameter	Straight lift with direct attachment	2 slings Direct attachment		3 or 4 slings with	n Direct attachment	
		Angle of leg fr	om vertical	Angle of le	g from vertical	
		0-45 deg.	45-60 deg.	0-45 deg.	45-60 deg.	
7	1.5 t	2.12 t	1.5 t	3.15t t	2.24 t	
7mm	1.2 t	1.69 t	1.2 t	2.52 t	1.79 t	
	2 t	2.8 t	2 t	4.2 t	3 t	
8mm	1.6 t	2.24 t	1.6 t	3.36 t	2.4 t	
10mm	3.15 t	4.25 t	3.15 t	6.7 t	4.75 t	
10111111	2.52 t	3.4 t	2.52 t	5.36 t	3.8 t	
13mm	5.3 t	7.5 t	5.3 t	11.2 t	8 t	
13111111	4.24 t	6 t	4.24 t	8.96 t	6.4 t	
16mm	8 t	11.2 t	8 t	17 t	11.8 t	
10111111	6.4 t	8.96 t	6.4 t	13.6 t	9.44 t	
19mm	11.2 t	17 t	11.2 t	23.6 t	17 t	
13111111	8.96 t	13.6 t	8.96 t	18.88 t	13.6 t	

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 5 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01 Dec 2024



# Grade 10 chain slings

Ratings for single and multi-leg chain slings within 60 Deg. Grade 10 chain slings *Please note:* 

SWL for 'Choker' hitch mode factors in each configuration given are shown in by the required 0.8 factor



and have been reduced

Chain sling details and configuration chart – Grade 10 Chains						
Chain Diameter	Straight lift with direct attachment			3 or 4 slings with	n Direct attachment	
		Angle of leg fr	om vertical	Angle of le	g from vertical	
		0-45 deg.	45-60 deg.	0-45 deg.	45-60 deg.	
C	1.4 t	2 t	1.4 t	2.9 t	2.1 t	
6mm	1.12 t	1.6 t	1.12 t	2.32 t	1.68 t	
	2.5 t	3.5 t	2.5 t	5.3 t	3.8 t	
8mm	2 t	2.8 t	2 t	4.24 t	3.04 t	
10mm	4 t	5.6 t	4 t	8.4 t	6 te.	
10111111	3.15 t	4.48 t	3.2 t	6.72 t	4.8 t	
13mm	6.7 t	10.6 t	9.5 t	14 t	10 t	
12111111	5.3 t	8.48 t	7.6 t	11.2 t	8 t	
16mm	10 t	14 t	10 t	21 t	15 t	
TOILILL	8 t	11.2 t	8 t	16.8 t	12 t	
20mm	16 t	22.4 t	16 t	33.6 t	24 t	
ZUITIII	12.8 t	17.92 t	12.8 t	26.88 t	19.2 t	

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 6 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01



## 7. Communications:

Note: The hand signals in the following pages are CGI representational of those found in BS 7121

Primary communication used for tower crane operations will be via radios.

See link to CPA TIN 017 for detailed information regarding the correct selection and use of.

In case of failure of radios then the following hand signals will be used to communicate with the tower crane operator

## **Hand signals:**



#### **Operations start:**

The slinger-signaller should raise their right hand with palm facing forward with the other hand perpendicular to the torso, palm down.



#### Hoist:

To hoist the load, the slinger-signaller should raise a fist above the head with their index finger pointed upwards, spinning in small circles.



#### 'Inch' the load:

'Inching' the load refers to slowly lifting the load.

To inch the load the slinger-signaller will raise their hand to head height & will clench and unclench their fist.

Process Owner: Head of Lifting Approved By: C. Hook Page: Page 7 of 118 Document No.: XXXX\_XXXX\_XXXX

Document Rev: 01
Date Approved: Dec 2024



# Hand signals:




## Lower steady:

To instruct the crane operator to lower the load at a steady rate, hold one arm down against the side of the body. Extend the other arm to the side of the body @ approx. 45 deg., hand closed, index finger pointing downwards & make circular movements with the forearm.



#### Slew in direction indicated:

To instruct the crane operator to slew the crane, the slinger-signaller should raise their forearm from the side of their body and holding the handout at elbow height with the palm facing downwards in left or right motion.





# Lowering boom while raising load: 'floating the load'

To instruct the crane operator to maintain the height of the load while lowering the boom i.e., sending the load away from the crane. Extend one arm to the side with hand clenched and thumb pointing downwards, while raising the other arm above shoulder height with hand clenched and index finger pointed up while making small circular movement with the forearm.





# Raising boom while lowering load: 'floating the load'

To instruct the crane operator to maintain the height of the load while raising the boom i.e., bringing the load towards the crane. Extend one arm to the side with hand clenched and thumb pointing upwards and extend the other arm to the side of the body @ 45 deg., hand closed, index finger pointing downwards while making circular movements with the forearm.

Document No.: XXXX\_XXXX\_XXXX

Document Rev: 01

Document Rev: 01
Date Approved: Dec 2024



# **Hand signals:**



## **Operations Cease:**

The cease operations signal is performed by extending the arms outwards and bringing them both to the centre of the torso and back out again.

Note:

'Operations cease' is to notify the crane operator that the lifting operation has been completed.



## **Operations stop:**

To indicate that the crane operator should stop, raise one hand just above head height with the palm open and the other hand at the side of the body.

Note:

'Operations stop' is used during a procedure and is usually followed by another instruction i.e., stop – slew in the direction indicated – stop – lower the load – stop



## Emergency stop:

To stop all operations immediately, raise both hands above the head with the palms open and facing forwards.

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 9 of 118 Document No.: XXXX\_XXXX\_XXXX

Document Rev: 01
Date Approved: Dec 2024



# **Hand signals**

'Trolley' jib only movement:



## Trolley in:

To instruct the crane operator to move the trolley 'in' along the jib, the slinger will raise fore arms to shoulder level and point thumbs 'inward' & towards each other.



## Trolley out:

To instruct the crane operator to move the trolley 'out' along the jib, the slinger will raise forearms to shoulder level and point thumbs 'outward' & away from each other.

#### 'Luffing' jib only movement:



## 'Jib' Up:

To instruct the crane operator to move the 'head' or 'jib' of the crane to a higher position the slinger will tap the head with one arm, extend the other with their thumb out & up, & move it in a 'up & down' motion.

Process Owner: Head of Lifting
Approved By: C. Hook
Page: Page 10 of 118

## 'Jib' Down:

To instruct the crane operator to move the 'head' or 'jib' of the crane to a lower position the slinger will tap the head with one arm, extend the other with their thumb out & down, & move it in an 'down & up' motion.

Document No.: XXXX\_XXXX\_XXXX

Document Rev: 01



#### 8. Wind Assessment:

The following is to be used as a 'General' guidance for wind assessment and by no means replaces site specific weather parameters or control measures stated in lift plans, schedules, and associated risk assessments.

When assessing the max. wind speeds and the effect on loads there are too many variables that need to be taken into consideration to allow definitive wind speeds for each load to be stated in this document.

Size, design & weight are just a few considerations that must be planned for .

The day's weather forecast must form part of the morning DABs

More often than not project lifting teams will need to complete an informal *POWRA* if the weather is unsettled.

When reviewing the safety of the lift in unsettled conditions the following points are to be considered (non-exhaustive):

- Weather conditions at time of lift What is the wind speed? Is there a chance of lightning or weather worsening during the anticipated time scale of the lift? Does the weather look like improving which would allow the lift to be performed at a later time during the working day?
- Path of the load and distance travelled Will the load be lifted in close proximity to temporary, permanent structures or sensitive areas i.e., Network Rail property etc. Is the load being lifted over a great distance so increasing the time it is 'in the air'?
- Height of the load when lifted Will the load become problematic based on the height it is being lifted from or to?
- Area of the load Is the load of a great area that could cause a 'windsail' effect?
- Weight & physical make-up of the load Is the load of such a weight that it can be 'taken' by the wind, conversely is the load of such a weight that it will become dangerous & uncontrollable if the wind causes 'spinning'.
- Configuration of the load Will the load require turning prior to delivery/install? Are there components of the lift that require calm conditions to achieve a safe install i.e., Cladding panel attachment?
- Configuration of the accessory arrangement Are the accessories of such a length that could cause a pendulum effect in unsettled conditions? Are there any engineering control methods involved that have their own max. wind speed limits i.e., Mechanical load control equipment
- Controlling the load Will additional load controls i.e., more taglines or operatives be required? Are these controls or operatives readily available? With the additional taglines or manual control measures, will this increase existing hazards and/or introduce new problems?

For industry guidance on tower cranes and wind conditions:

- > TCIG TIN 020 The Effect of Wind on Tower Cranes In Service
- TCIG TIN 025 Luffing Jib Tower Cranes Precautions for Operators Working at or near Minimum Radius in Strong Winds
- ➤ TCIG TIN 027 Tower Crane Out-of-Service Wind Speeds
- Liebherr Influence of wind on crane operations

Process Owner: Head of Lifting
Approved By: C. Hook
Page: Page 11 of 118

Document No.: XXXX\_XXXX XXXX Document Rev: 01

Date Approved:



## 9. General safety considerations:

Please note:

The following is to be used as a 'General' guidance for all lifting operations and by no means replaces site specific safety considerations or control measures stated in lift plans, schedules, and associated risk assessments.

## The work area set up:

- Refer to the lift plan and form an exclusion zone(s) and/or restricted zone(s) as required around lifting & delivery areas. Ensure all third parties are removed from lifting operations work area.
- Ensure that any exclusion zone and/or restricted zones are clearly identified using correct signage, segregated using physical barriers and, if required, suitably marshalled.
- As far as is practicable ensure that all background noise is kept to a minimum. If necessary, stop all noisy works during the lifting operation while communicating with the Tower Crane operator.
- Lifting to and from delivery vehicles [inclusive of points above]:
  - > Before mounting the vehicle make sure there is a suitable access/egress point.
  - Check that the edge protection is of a suitable height to allow the lifting operation to be performed without slinger's position being compromised, i.e., slinger being above the handrail.
  - Ensure only the accessories required are taken onto the vehicle. If necessary, have someone on hand to pass accessories to the slinger to negate multiple accessories being taken onto the wagon forming potential trip hazards when stored on the vehicle or the slinger having hand's full whilst attempting to gain access to the vehicle
- Slingers are to familiarise themselves with the work area to be aware of their positioning in relation to:
  - ➤ The raising and lowering of any load A safe space to stand.
  - Potential obstacles.
  - Escape routes in case they must 'get out of the way' quickly if the load spins or doesn't act as anticipated i.e., Bundled loads gathering, loads 'turning' when taking from the horizontal to the vertical, hook block & accessories not correctly sited over the centre of gravity.

## The load:

- Only lift loads that are in the project approved Schedule of Lifts if unsure, consult the Lifting Supervisor or Appointed person so that the relevant information can be provided.
- Assess the weight & CoG of the load if unsure, again, consult the Lifting Supervisor or Appointed person so that the relevant information can be provided.
- Path of the load to be planned to ensure that the lifting operation is performed in a timely manner to negate the load being 'in the air' for any longer that it must
- Ensure the load will stay together during lifting operations and that all loose materials are removed from load or housed and retained securely within the load prior to lift.
- Ensure the load is stable when lowered and landed, prior to releasing the weight and lowering fully. i.e., employ a ratchet strap around the load to negate 'tipping' or 'spreading' [see opposite].

Process Owner: Head of Lifting Approved By: C. Hook Page: Page 12 of 118 Document No.:
Document Rev:

XXXX\_XXXX\_XXXX
01



- If the load is repeatedly lifted, ensure there is sufficient space round the load to facilitate safe re-slinging
- When landing loads near pedestrian walkways be mindful of the possible 'fall' area of the load if it were to collapse after accessories have been removed.
- If the load requires to be landed on timbers or spacer 'chocks', make sure they are of such a size to allow a safe removal of the accessories. Do not drag accessories free from any load.

#### The accessories:

- All accessories used must have a current RoTE and must be suitably identified as per industry regulations.
- Prior to attachment and after removal of the accessories, they must be visually checked for any deformation or damage that could affect their continued safe use. If any damage is found then the Lifting Supervisor is to be informed, the accessory removed from service, tagged as 'Not for use' and stored away in a suitable 'Quarantine box'.
- Ensure the correct accessory is used for the lifting operation—if the correct accessory is not available then do not attempt the lift with 'other' accessories and consult your Lift supervisor and/or Appointed person.
- Check that the accessories to be used are equal to or greater than the WLL stated for use as per the lifting schedule or plan.
- Verify that the angle of use of the accessory is within an 'excluded or beta' angle of 0-45 Deg.
- As far as practicable, protect lifting accessories to ensure they are not damaged by sharp or burred edges and that they are free to align correctly.

#### The lift:


- Clear a safe lifting path across the project. Lifting over the head of personnel should be minimised as far as is reasonably practicable
- Make sure operatives nearby are aware that the lift is being performed. Issue audible [electronic whistles etc.] and verbal warnings to those in the immediate areas.
- Check that all operatives are clear of the path of the load
- Attach the accessories to the load as per the lift plan. If it
  is found that the planned lifting arrangement is not
  workable, inform the Lifting Supervisor and Appointed person for further guidance and
  instruction. Do not attempt the lift!

#### Note:

When double wrapping ensure you 'lay' the accessories 'side by side' and ensure they don't cross over on the underside of the load.

- Conduct a 'test' lift of the load prior to movement across the project, to check balance, centre of gravity, stability and attachment of accessories is suitable to ensure a safe lift across the project
- Sling the load to suit a level lift





Incorrect Correct

Process Owner: Head of Lifting
Approved By: C. Hook
Page: Page 13 of 118

Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX
01



• Keep hands, fingers, and limbs free from the lifting accessories and choke points during hoisting – Hands Off!

• Prior to lifting the load, move away from the load to ensure clothing and any tools that may be carried do not become entangled – **Step Away!** 

When lifting or landing loads do not stand under the load or in any area where there is a danger of being struck or trapped by load when lowering – Safe Space!

• If required apply load control measures [taglines/push-pull poles] to assist in configuration of the loads

Please note:

When using taglines never wrap them around your hand, wrist, or body to assist in control of the load.

## 10. <u>Hands Off – Step Away - Safe space:</u>



Hands off, Step Away, Safe Space [HOSASS] is an industry initiative concerning, primarily, the historical behaviour of slingers and 'other' operatives in and around lifting operations and reducing, via various control measures, the physical interface between lift team members and the load.

The aim is to highlight to all lift team members the considerations required, from the conception of the works though to final realisation of a lifting operation, for the safe positioning, and the positioning of others, when:

- Slinging loads what actions are to be taken in the immediate area around the load and the control measures to be implemented.
- Hoisting loads considerations of physical position in relation the load so to reduce the risk of being struck due to unexpected load movement from the test lift through to the final hoisting.
- Controlling the configuration of the load – how to, when to and what with.
- Lowering and landing the load identifying at what point to approach and how to guide the load to final delivery area.
- Leaving the load ensuring integrity of stability before 'walking away'.



Process Owner: Head of Lifting
Approved By: C. Hook
Page: Page 14 of 118

Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01





It is not a new concept to avoid putting yourself in harm's way. Despite this, it is common to see people involved in lifting operations placing themselves in locations where, if something went wrong, they could easily be hurt, or worse.

If something appears to be going wrong, it is also common to see people acting instinctively to try and sort the issue, thereby exposing themselves to further danger, rather than stopping the lift and

remaining in a safe place until the load is safe to approach. Loads are more likely to move unexpectedly during the initial stages of a lifting operation, particularly when first lifted up (including for trial lift), compared to later stages of a lift.

**HOSASS** works on the simple principle of personnel assessing their surroundings, identifying hazards nearby, and moving to a place of safety, whenever reasonably practicable away from the load before loads are lifted up.



#### Personnel should only ever have their hands on a load through necessity, and not habit.

Prior to starting

Assess your surroundings and identify potential nearby hazards, for example any potential for slips, trips, and falls, crushing zones, falling objects, adjacent plant and activities, and areas where you may not be visible to others. Focus on eliminating



Link to the ILLAPG resource section attending to 'Hands Off – Step Away – Safe Space' here

Process Owner: Head of Lifting
Approved By: C. Hook
Page: Page 15 of 118

Document No.: XXXX\_XXXX\_XXXX

Document Rev: 01



The schedules				
Page	Title:	Page	Title:	
18.	Timber – Packs of ply	61.	Formwork – Column boxes with proprietary clamp/attachments	
19.	<u>Timber – Bundles, Scaffold boards, 4' x 2'</u>	64.	Slab formwork – Tables with proprietary lifting hook - 'C' Hook	
20.	Reinforcement – Straight lengths	66.	<u>Precast concrete elements – Kentledge or 'Kelly' concrete block</u>	
21.	Reinforcement - Links	68.	Precast concrete elements – Legato or 'Lego' blocks	
22.	Reinforcement – 'L'-Shape bundles	70.	Precast concrete elements – Access chamber rings	
23.	Reinforcement - Mesh packs	71.	<u>Precast concrete elements – Access chamber</u> <u>cover slabs</u>	
24.	Prefabricated 'cages' – Wall sections	72.	<u>Precast concrete elements – Vertical Concrete</u> <u>Barriers/Vehicle Crash Barriers (VCB's)</u>	
28.	Reinforcement - Prefabricated 'cages' - Columns	75.	Precast concrete elements – Stair units	
30.	Prefabricated 'cages' – Beams	78.	Precast concrete elements – Intermediate landing units] / Capping slab units	
31.	Prefabricated 'cages' – Pile capping beams	80.	Precast concrete elements – Concrete drainage pipes [Single]	
32.	<u>Transport stillages – Box/Bin</u>	82.	Clay pipe [drainage] - Bundle	
33.	<u>Transport stillages – Open/Post/Pallett</u>	84.	Steel pipe [drainage] - Bundle	
34.	Containment accessories – Good cages	86.	Scaffolding tubes – Stillages 5' to 10' only	
35.	Containment accessories – Wheeled bins	88.	Scaffold tubes – Bundles 7' to 21' only	
36.	Containment accessories – Brick Fork cages	90.	Site plant – Mobile tower lights	
37.	Containment accessories – Concrete Skips – Bale Arm	91.	<u>Site plant - Compressors</u>	
39.	Containment accessories – Waste skips with rated/tested lifting points	92.	Site plant – Welding set generator	
40.	Containment accessories – Self Discharge Boat skips	93.	Site plant – Compactor plate	
43.	<u>Containment accessories – Gas bottle cages - Single &amp; multi point</u>	94.	Site plant – Drum Roller	
45.	Containment accessories – Fuel Bowser	95.	Site plant – Power trowel [float]	
47.	Containment accessories – Jetwash Bowser	96.	Steel beams - Girders, H section, I section, U beams, Lintels	
49.	Containment accessories – FIBC Bags (Fabric bags)	98.	Loading platform	
51.	Formwork components – Ledger frames	101.	Carrying of personnel – Special note	
52.	Formwork components – Primary & secondary Beams	102.	Carrying of personnel - Use of Suspended Personnel Carrier	
53.	Formwork components – Support legs [outer and inner components]	107.	MEWPs	
54.	Formwork components – Panel stacks	109.	Toolbox	
56.	Formwork components – 'Strongback' bundles	111.	Transformer box up to 20kva	
58.	Formwork – Panels with proprietary clamps in use	112.	Pedestrian barriers	

Process Owner: Head of Lifting Approved By: C. Hook Page: Page 16 of 118

Document No.: XXXX\_XXXX\_XXXX Document Rev: 01

Dec 2024

Date Approved:



The sch	The schedules					
Page	Title:	Page	Title:			
113.	Heras fence panels - Stillage & loose bundles					
114.	<u>Excavator buckets</u>					
115.	<u>Timber 'Ekki' Mats</u>					
117.	Blank template					

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 17 of 118

Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01



#### Load description: Timber – Packs of ply



## Slinging methodology:

- 4 leg chain slings will be attached to hook block of the crane. Only 2 legs required so any unused chains will be hung back to the master ring.
- II. 2no. webbing slings min WLL 3t of sufficient length will be attached to the ply pack in a double wrap choke configuration.
- III. Hooks of chain slings will then be attached to the webbing slings.
- IV. Ratchet strap or securing banding to be used around load.

Lift Category:	Basic				
Dimensions of load:	Various dimensions: Typically, 1.6m [h] x 2.4m [l] x 1.2m [w] for standard pack of ply				
Weight of Load	Typically, 1.6 t for 18mm ply but up t	to 1.8 t			
Lifting accessories	From hook block:	WLL x Mode Factor	Resulting SWL		
used with weights of accessories:	4 Leg chain slings WLL 8.4 t @ 103kg	4 leg chain slings with 2 legs in use - WLL of one leg multiplied by 1.4 = 4.41 t	3.36 t over all		
	2no. webbing slings 10m @ 7kg  Gross weight inc. 10% FOS: 2.101 t	2 webbing slings used a set in a choke configuration = [WLL	accessories stated		
Alternative methodology:	If size of hook block allows, then the webbing slings can be directly attached.  DO NOT OVERCROWD THE BLOCK				
Safe lifting considerations:	<ol> <li>Check underside of ply for a during transit or storage.</li> </ol>	nny materials that may have adhe	ered themselves		
	II. Securing banding or ratchet strap to be used around the pack.				
	III. When slinging 'used' ply ensure that all elements of the load are captured by using securing banding around the pack.				
	IV. Check integrity of landed load after removal of access	sories in case of collapse.			

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 18 of 118 Document No.:
Document Rev:

XXXX\_XXXX\_XXXX 01



#### Load description: Timber - Bundles i.e., Scaffold boards, 4 x 2, 6 x 3, loose timber bundles, etc



## Slinging methodology:

- I. 4 leg chain slings will be attached to hook block of the crane.
- II. Any unused chains will be hung back to the master ring.
- III. 2no. webbing slings min WLL 3t of sufficient length will be attached to the pack in a double wrap choke configuration.
- IV. Hooks of chain slings will then be attached to the webbing slings.
- V. Ratchet strap or securing banding to be used around load.

Lift Category:	Basic					
Dimensions of load:	Various dimensions: Typically, 1000mm [h], 1000mm [w] & 4800mm [l] for standard pack of 4' x 2' or 6' x 3'					
Weight of Load	Typically, no more than 2.5 t for dim	ensions given				
Lifting accessories	From hook block:	WLL x Mode Factor	Resulting SWL			
used with weights of accessories:	4 Leg chain slings WLL 8.4 t @ 103kg	4 leg chain slings with 2 legs in use - WLL of one leg multiplied by 1.4 = 4.41 t				
	2no. webbing slings 10m @ 7kg		3.36 t over all			
	Cross weight in a 100/ FOS: 2 971 t	2 webbing slings used a set in a choke configuration = [WLL of one sling multiplied by 1.4]	accessories stated			
	Gross weight inc. 10% FOS: 2.871 t	x .8 = 3.36 t				
Alternative methodology:	If size of hook block allows, then the webbing slings can be directly attached.  DO NOT OVERCROWD THE BLOCK					
Safe lifting considerations:						
	II. Securing banding or ratche	t strap to be utilised around the l	oad.			
	III. Check integrity of landed load after removal of accessories in case of collapse.					
	IV. When slinging 'used' timbers ensure that all elements of the load are captured by utilising securing banding or ratchet strap around the pack.	timbers ensure that all elements of the load are captured by utilising securing banding or ratchet				

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 19 of 118 Document No.: Document Rev: XXXX\_XXXX\_XXXX 01



# Loads description: Reinforcement – Straight lengths



# Slinging methodology:

- 4 leg chain slings will be attached to hook block of the crane. Only 2 legs are required so any unused chains will be hung back to the master ring.
- II. 2 legs of the chain sling will be attached to the load in a double wrap - choke configuration.
- III. Do not lift from tying wire

Lift Category:		Basic			
Dimensions of load:	Typically, in lengths from 6m to 12m with diameters of 500mm				
Weight of Load	Typically, 2.5 t for 12m lengths of 25m	m reinforcement			
Lifting accessories	From hook block: 4 Leg chain slings WLL 8.4 t @ 103kg	WLL x Mode Factor	Resulting SWL		
used with weights of accessories:	Gross weight inc. 10% FOS: 2.863 t	4 leg chain slings with 2 legs in use in a choke configuration – [WLL of one leg multiplied by 1.4] x .8 = 3.528 t	3.528 t Over all accessories stated		
Alternative methodology:	Collar chains can be used around the load in the same configuration. min WLL 3.15 t ea.				
Safe lifting considerations:	<ol> <li>Check the bundle for any short captured by the accessories.</li> </ol>	t lengths of reinforcement that	are not		
	II. Sling to suit a level load along the length of the bundle. Where necessary a third chain can be employed to achieve the level configuration. i.e., third chain used in the middle of the load to minimise 'sagging' to allow a safe landing.				
	III. When landing the load ensure that suitable timbers/chocks are employed to enable a safe re-slinging of the load.				
	IV. Leave a suitable gap between landed bundles to ensure a safe access to resling. Considerations are to be made to the spread of the load when securing wire is removed.				
	V. Do not stack bundles more than 2 bundles high and ensure that timbers of suitable strength and length are employed to enable safe stacking.				
	VI. When landing loads ensure enough room is left between the bundles to allow for safe access for slinger when slinging again.				

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 20 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01 Dec 2024



#### Loads description: Reinforcement - Links



# Slinging methodology:

- 4 leg chain slings will be attached to hook block of the crane. Only 2 legs are required so any unused chains will be hung back to the master ring.
- II. 2 legs of the chain sling will be attached to the load in a single wrap captured choke configuration.
- III. Do not lift from tying wire

Lift Category:	Basic				
Dimensions of load:	Various with no typical sizes				
Weight of Load	Typically, no more than 2 t				
Lifting accessories	From hook block:	WLL x Mode Factor	Resulting SWL		
used with weights of accessories:	4 Leg chain slings WLL 8.4 t. @ 103kg  Gross weight inc. 10% FOS: 2.313 t	4 leg chain slings with 2 legs in use in a choke configuration – [WLL of one leg multiplied by 1.4] x .8 = 3.528 t	3.528 t Over all accessories stated		
Alternative methodology:	Collar chains can be used around the load in the same configuration. min WLL 3.15 t ea.  Additionally, 4 legs of chain sling can be used at each corner of the links bundle in a choke configuration				
Safe lifting considerations:	<ol> <li>When landing the load ensure that suitable timbers/chocks are employed to enable a safe re-slinging of the load.</li> </ol>				
	II. Leave a suitable gap between landed bundles to ensure a safe access to resling.				
	III. Link bundles are not to be stacked atop each other or other loads.				
	IV. Sling bundles to suit a level co	nfiguration.			

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 21 of 118

Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01



#### Loads description: Reinforcement – 'L'-Shape bundles



## Slinging methodology:


- I. 4 leg chain slings will be attached to hook block of the crane. Only 2 legs are required so any unused chains will be hung back to the master ring.
- II. 2 legs of the chain sling will be attached to the load in a double wrap – choke configuration.
- III. Spacing of the chains to suit a level load.
- IV. Do not lift from tying wire

G		IV. Do not lift from tying wire			
Lift Category:		Basic			
Dimensions of load:	Various with no typical sizes	Various with no typical sizes			
Weight of Load	Typically, no more than 2 t				
Lifting accessories	From hook block: 4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor	Resulting SWL		
used with weights of accessories:	103kg	4 leg chain slings with 2 legs in use in a choke configuration – [WLL of one leg multiplied by 1.4]	3.528 t Over all accessories stated		
	Gross weight inc. 10% FOS: 2.313 t	x .8 = 3.528 t	Stated		
Alternative methodology:	Collar chains can be used around the load in the same configuration. min WLL 3.15 t ea.				
Safe lifting considerations:	I. When landing the load of timbers/chocks are emposafe re-slinging of the lo	ployed to enable a 🖊 🥻 🧻			
	II. Leave a suitable gap (60 bundles to ensure a safe	/ 4			
	III. Sling bundles to suit a level configuration. Where necessary a third chain can be employed to achieve the level configuration.				
	Please note: Bundles are <b>not</b> to be slung so the of the bundles are facing either dor upwards. Slinging in this configuration will landing problematic due to load when landing.	ownwards make			

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 22 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01



#### Loads description: Reinforcement - Mesh packs



Hook attachment to be at interserction of the 5th cross and the 3rd line wire

## Slinging methodology:

- I. 4 leg chain slings will be attached to hook block of the crane.
- II. Chain slings will be attached through the pack of mesh in a captured choke configuration.
- III. Placement of the chains should be at the intersections of the 5th cross wire and the 3rd line wire.



IV. Do not lift from tying wire.

Lift Category:	Basic				
Dimensions of load:	Typically, 2400mm [w] x 4800mm [l] x 6000 mm [ h]				
Weight of Load	Typically, 2.3 t for fifty sheets of A393	3 mesh sheets			
Lifting accessories	From hook block: 4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor	Resulting SWL		
used with weights of accessories:	103kg  Gross weight inc. 10% FOS: 2.644 t [ru]	4 leg chain slings with 4 legs in use – WLL multiplied by .8 = 6.72 t	6.72 t over all accessories stated		
Alternative methodology:	Collar chains or can be used around ea.	the load in the same configuration	on. min WLL 3.15 t		
	Please note: Some pre-slung packs are slung with short wire bonds. Ensure prior to lifting that they are positioned as per the diagram above and that they are of sufficient WLL after mode factors considered to lift the load				
Safe lifting considerations:	I. When landing the load ensu enable a safe re-slinging of t	re that suitable timbers/chocks a	are employed to		
	II. Leave a suitable gap between landed stacks to ensure a safe access to resling.				
	IV. Do not stack mesh more than 1500mm in height to avoid the ends of the mesh at head height.				
	V. Utilise protective covering a	it mesh ends when landed.			

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 23 of 118 Document No.:
Document Rev:

XXXX\_XXXX\_XXXX 01




## Loads description: Reinforcement - Prefabricated 'cages' - Wall sections

#### Special note:

Following images & descriptions are **examples** of 'common' lifting arrangements utilized for these lifts. Please refer to local TW's design and confirmed arrangements to define configuration of lift

Section



Slinging methodology: Double skinned walls [typically for double skin walls < 4m long]

- Check cage has TW confirmation of 'able to lift'
- II. Attach 4 leg chain sling to hook block of crane. 2 legs only in use so hang spares back to the master ring.
- III. Feed chains through wall section and attach to identified lifting points as per TW design for the cage.

<u>Slinging methodology: Single skinned walls</u> [typically for single skin walls < 4m long]

- I. Check cage has TW confirmation of 'able to lift'
- II. Attach 4 leg chain sling to hook block of crane. 2 legs only in use so hang spares back to the master ring.
- III. Feed chains through wall section and attach to identified lifting points as per TW design for the cage.

Slinging methodology: Double skinned walls [typically for double skin walls > 4m long]


- I. Check cage has TW confirmation of 'able to lift'
- II. Attach 4 leg chain sling to hook block of crane. 2 legs only in use so hang spares back to the master ring.
- III. Attach hooks of chain sling to attachment points of lifting beam/frame.
- IV. Raise beam to allow safe attachment of ancillary accessories from underside of lifting beam/frame.
- V. Feed ancillary accessories through the wall section and attach to identified lifting points as per TW design for the cage

Process Owner: Head of Lifting
Approved By: C. Hook
Page: Page 24 of 118

Document No.: XXXX\_XXXX\_XXXX
Document Rev: 01
Date Approved: Dec 2024



## Loads description: Reinforcement - Prefabricated 'cages' – Wall sections



Slinging methodology: Single skinned walls [typically for single skin walls > 4m long]

- I. Check cage has TW confirmation of 'able to lift'
- II. Attach 4 leg chain sling to hook block of crane. 2 legs only in use so hang spares back to the master ring.
- III. Attach hooks of chain sling to attachment points of lifting beam/frame.
- IV. Raise beam to allow safe attachment of ancillary accessories from underside of lifting beam/frame.
- V. Attach ancillary accessories to identified lifting points as per TW design for the cage

Lift Category:	Intermediate			
Dimensions of load:	Various dimensions over assorted designs: _mm [w] x _mm [h] x _mm [l]			
Weight of Load	Various weights over assorted designs _ t			
Lifting accessories used with weights of	<b>Direct attachment</b> : From hook block >	4 leg chain slings with 2 legs in use in direct attachment = WLL of one multiplied by 1.4 = 4.41 t  4 leg chain slings with 2 legs in use in direct attachment = WLL of one multiplied by 1.4 = 4.41 t  Lifting beam/frame as per designed use  [list ancillary accessories giving mode factors employed to the WLL]	Resulting SWL	
accessories:	4 Leg chain slings WLL 8.4 t @ 103kg  Gross weight inc. 10% FOS: _t		4.41 t over all accessories stated	
	Ancillary attachment via Lifting beam/frame:  From hook block > 4 Leg chain slings WLL 8.4 t @ 103kg		_t over all accessories stated	
Alternative methodology:	Various methodologies can be used but note that all alternative methodologies should have gone a TW's approval process and confirmed that lift can take place.			

Process Owner: Head of Lifting
Approved By: C. Hook
Page: Page 25 of 118

Document No.: XXXX\_XXXX XXXX Document Rev: 01

Dec 2024

Date Approved:




#### Loads description: Reinforcement - Prefabricated 'cages' – Wall sections

# Safe lifting considerations:

- I. Ensure the attachment points for the accessories have been clearly identified and that a *TWC* approval for lifting is in place.
- II. Check attachment points and surrounding areas for any loose tying wire connections. If found inform the Lift Supervisor and do not lift.

#### IF UNSURE OF ATTACHMENT CONSULT THE LIFT SUPERVISOR FOR ADVICE.

- III. Prefabrication area to be as close as possible to install area to negate lifting the load across project. Minimise distance to be travelled with the wall section.
- IV. When standing the wall section from horizontal to the vertical monitor the position of the block in relation to the bottom of the wall section to keep the wall section from 'swinging' when fully raised.
- V. Constant monitoring and adjustment are to be performed in 'slew' and 'boom' positioning to allow a safe 'standing' of the load
- VI. Attention to be paid to the lower sections of the vertical bars for any unanticipated 'flexing' that could cause a spring of the wall or undue swinging
- VII. When using a lifting beam, check the frame for any splits or creases in the structure that could affect integrity of the beam.
  - Has the beam been painted lately that could cover up deformities?
- VIII. Ensure the length of the chain sling attaching to the cage & top of the beam is of sufficient length to allow for the chain to be within a 0 to 45 deg. excluded angle.
  - IX. Ensure the hooks of the chain sling fit into the lifting points situated to the top of the beam. If required use bow shackles, or similar, to affect a correct attachment of the crane chain slings.
  - X. Ensure the ancillary accessory attachment and arrangement to the underside of the beam is 'like for like' and uniform in dimension and WLL.



## DO NOT MIX & MATCH THE ACCESSORIES

- XI. Attention to be paid to any ancillary accessories within the wall structure, check path of the accessory to ensure it doesn't compromise the structure of the wall.
- XII. Ensure scaffold tubes and timbers are not used as load bearing points in any lifting arrangements.

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 26 of 118

Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01



#### Loads description: Reinforcement - Prefabricated 'cages' - Wall sections

# Additional information:

# Reference weights:


Reinforcement weight per square meter (Kg/m2)				
_	Bar spacing			
Bar diameter	100mm	150mm	200mm	250mm
10mm	6.16 kg/m2	4.11 kg/m2	3.08 kg/m2	2.46 kg/m2
12mm	8.88 kg/m2	5.92 kg/m2	4.44 kg/m2	3.55 kg/m2
16mm	15.79 kg/m2	10.53 kg/m2	7.9 kg/m2	6.32 kg/m2
20mm	24.66 kg/m2	16.44 kg/m2	12.33 kg/m2	9.86 kg/m2




## Loads description: Reinforcement - Prefabricated 'cages' - Column

Following are **examples** of lifting arrangments, *Please refer to local TW's design and confirmed arrangements for defined configuration of lift.* 


#### 'Square column



#### 'Rectangular column':



#### 'Circular column'



Process Owner: Head of Lifting Approved By: C. Hook Page: Page 28 of 118

## **Vertical lifting:**

# Slinging methodology: - 2 attachment points

[Covering 'Square' & 'Rectangular' cages]

- I. Check cage has TW confirmation of 'able to lift'
- II. Attach 4 leg chain sling to hook block of crane. 2 legs only in use so hang spares back to the master ring.
- III. Feed chains through column and attach to identified lifting points as per TW design for the cage.

### Slinging methodology: - 4 attachment points


[Covering 'Square' and 'Circular' cages]

- Check cage has TW confirmation of 'able to lift'
- II. Attach 4 leg chain sling to hook block of crane.
- III. Feed chains through column and attach to identified lifting points as per TW design for the cage.

## **Horizontal lifting:**

- I. Check cage has TW confirmation of 'able to lift'
- II. Attach 4 leg chain sling to hook block of crane. Dependant on design, if only 2 legs are in use, then hang spares back to the master ring.
- III. Attach hooks of chain sling to the identified lifting points as per TW design for the cage in a choke configuration.

# <u>Plan view of example arrangements for horizontal lifting:</u>



Document No.: XXXX\_XXXX\_XXXX

Document Rev: 01



Loads description: Reinforcement - Prefabricated 'cages' - Column				
Lift Category:	Intermediate			
Dimensions of load:	Various dimensions over assorted	designs: _mm [w] x _mm [h] x _	_mm [l]	
Weight of Load	Various weights over assorted des	igns_t		
Lifting accessories used with	From hook block >  4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor 4 leg chain slings with 2 legs	Resulting SWL	
weights of accessories:	103kg	in use in a choke configuration – [WLL of one leg multiplied by 1.4] x .8 = 3.528 t	3.528 t over all accessories stated	
	Gross weight inc. 10% FOS: _t	4 leg chain slings with 4 legs in use – WLL multiplied by .8 = 6.72 t	6.72 t over all accessories stated	
Alternative methodology:	Various methodologies can be used. All must have gone a TW's approval process by <i>TWC.</i> [Temporary Works Coordinator] and confirmed that lift can take place			
Safe lifting considerations:	I. Ensure the attachment points for the accessories have been clearly identified and that a <i>TWC</i> approval for lifting is in place.			
	II. Check attachment points and surrounding areas for any loose tying wire connections. If found inform the Lift Supervisor and do not lift.			
	IF UNSURE OF ATTACHMENT	CONSULT THE LIFT SUPERVISO	OR FOR ADVICE.	
	<ul> <li>III. Prefabrication area to be as close as possible to install area to negate lifting the load across project. Minimise distance to be travelled with the column section.</li> <li>IV. When standing the column section from horizontal to the vertical monitor the position of the block in relation to the bottom of the column section to keep the column from 'swinging' when fully raised.</li> </ul>			
	V. Attention to be paid to the accessories within the column structure, check path of the accessory to ensure it doesn't compromise the integrity of the columns structure i.e., cause 'rebar' to bend.			
		adjustment are to be performed v a safe 'standing' of the column	in boom/hook	
		e lower sections of the vertical ba at could cause a spring of the col		

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 29 of 118

Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01



#### Loads description: Reinforcement - Prefabricated 'cages' - Beams



## Slinging methodology:

- Check cage has TW confirmation of 'able to lift'
- II. Attach 4 leg chain sling to hook block of crane
- III. Attach hooks of chain sling to identified lifting points as per TW design for the cage.

Lift Category:	Basic				
Dimensions of load:	Various dimensions over assorted designs: _mm [w] x _mm [h] x _mm [l]				
Weight of Load	Various weights over assorted desig	ns_t			
Lifting accessories	From hook block > 4 Leg chain slings WLL 8.4 t @	WLL X Mode Factor Resulting SWL			
used with weights of accessories:	103kg  Gross weight inc. 10% FOS: _t	4 leg chain slings as per design use	8.4 t over all accessories stated		
Alternative methodology:	Various methodologies can be used, but all must have gone a TW's approval process by TWC. [Temporary Works Coordinator]				
Safe lifting considerations:	I. Ensure the attachment points for the accessories have been clearly identified and that a <i>TWC</i> approval for lifting is in place.				
	II. Check attachment points and surrounding areas for any loose tying wire connections. If found inform the Lift Supervisor and do not lift.				
	IF UNSURE OF ATTACHMENT CONSULT THE LIFT SUPERVISOR FOR ADVICE.				
	III. Prefabrication area to be as close as possible to install area to negate lifting the load across project. Minimise distance to be travelled with the beams section.				
	sufficient space around the	ench or foundation scenarios en e beam and adjacent area for sa installation operative at risk of	fe access to allow		
	V. Ensure there is easy access accessories	to the attachment points to all	ow safe removal of		


Process Owner: Approved By: Page: Head of Lifting C. Hook Page 30 of 118

Document No.: Document Rev: Date Approved:

XXXX\_XXXX\_XXXX 01 Dec 2024



# Loads description: Reinforcement - Prefabricated 'cages' - Pile capping beams





Plan view of a typical pad foundation cage up to 3m long, 3m wide or 2000kg

## Slinging methodology:

- I. Check cage has TW confirmation of 'able to lift'
- II. Attach 4 leg chain sling to hook block of crane.
- III. Attach hooks of chain sling to identified lifting points as per TW design for the cage.

Lift Category:	Basic			
Dimensions of load:	Various dimensions over assorted designs: _mm [w] x _mm [h] x _mm [l]			
Weight of Load	Various weights over assorted desig	ns_t		
Lifting accessories	From hook block > 4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor	Resulting SWL	
used with weights of accessories:	hts of	4 leg chain slings as per design use	8.4 t over all accessories stated	
Alternative methodology:	Various methodologies can be used, but all must have gone a TW's approval process by TWC. [Temporary Works Coordinator]			
Safe lifting considerations:	· ·	<ul> <li>I. Ensure the attachment points for the accessories have been clearly identified and that a <i>TWC</i> approval for lifting is in place.</li> <li>II. Check attachment points and surrounding areas for any loose tying wire connections. If found inform the Lift Supervisor and do not lift.</li> </ul>		
	IF UNSURE OF ATTACHMENT C	ONSULT THE LIFT SUPERVISO	R FOR ADVICE.	
		s close as possible to install are nimise distance to be travelled v	•	
	sufficient space around the	nch or foundation scenarios en beam and adjacent area for sa installation operative at risk of	fe access to allow	
	V. Ensure there is easy access accessories	to the attachment points to all	ow safe removal of	

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 31 of 118 Document No.:
Document Rev:
Date Approved:

XXXX\_XXXX\_XXXX 01 Dec 2024



# Loads description: Transport stillages – Box/Bin



## Slinging methodology:

- 4 leg chain slings will be attached to hook block of the crane. Only 2 legs in use so hang the unused chains back to the master ring.
- II. Attach the chains slings to the stillage by feeding the chain under the stillage and taking a 'Turn' around the legs/feet.
- III. Make sure the 'turn' is taken around opposite legs/feet in the diagonal.


Lift Category:		Basic		
Dimensions of load:	Various dimensions: Typically, 600mm [h] x 800mm [w] x 800mm [l]			
Weight of Load	Typically, no more than 1 t [base	ed on standard stillage WLL]		
Lifting accessories	From hook block:	WLL x Mode Factor	Resulting SWL	
used with weights of	4 Leg chain slings WLL 8.4 t @ 103kg	4 leg chain slings with 2 legs in use in a choke configuration –	3.528 t Over all	
accessories:	Gross weight inc. 10% FOS: 1.124 t [ru]	[WLL of one leg multiplied by 1.4] x .8 = 3.528 t	accessories stated	
Ancillary Equipment	Use closed mesh netting to negate any lightweight materials being blown from the confines of the stillage. When using a net covering ensure the net is secured to the body of the stillage.			
Safe lifting considerations:				

Process Owner: Head of Lifting Approved By: C. Hook Page: Page 32 of 118

Document No.: XXXX\_XXXX\_XXXX Document Rev: 01



# Loads description: Transport stillages – Open/Post



# Slinging methodology:

- 4 leg chain slings will be attached to hook block of the crane. Only 2 legs in use so hang the unused chains back to the master ring.
- II. 2no. webbing slings min WLL 2t of sufficient length will be attached to the stillage in a double wrap – choke configuration.
- III. Hooks of chain slings will then be attached to the webbing slings.

Lift Category:		Basic		
Dimensions of load:	Various dimensions: Typically for stillage, 1000mm [ h] x 1400mm [w] x 1030mm [l]			
Weight of Load	Typically, no more than 1 t [based o	n standard stillage WLL]		
Lifting accessories	From hook block:	WLL x Mode Factor	Resulting SWL	
used with weights of accessories:	4 Leg chain slings WLL 8.4 t @ 103kg	4 leg chain slings with 2 legs in use - WLL of one leg multiplied by 1.4 = 4.41 t	2.24 t over all	
	2no. webbing slings 8m @ 7kg  Gross weight inc. 10% FOS: 1.124 t [ru]	2 webbing slings used a set in a choke configuration = [WLL of one sling multiplied by 1.4] x .8 = 2.24 t	accessories stated	
Alternative methodology:	If size of hook block allows, then the webbing slings can be directly attached.  DO NOT OVERCROWD THE BLOCK			
Safe lifting considerations:	I. Sling positions to suit a leve	el load.		
constact actions.	II. Securing banding or ratchet strap utilised to ensure integrity of the load.  III. Check condition of the stillage prior to lifting.  Integrity of the feet?  Splits, dents, and creases that could affect the integrity of the structure when slinging?			
	IV. Always check the feet of the stillage to just make sure that stones or mud etc./have not adhered themselves to the inside of the feet.			
		of the legs for any small objects, ald fall out once stillage is raised		
	Special note:			
	If lifting double stacked stillages i.e., from the bed of delivery wagon, then this should be a low-level lift only and the stillages separated as soon as possible to negate overloading the bottom stillage.  Checks to be made that not only are any pre slung slings used are of sufficient WLL to take the weight of both stillages, but that in date RoTE's of the slings have been checked prior to lifting.			

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 33 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01 Dec 2024



# Loads description: Containment accessories – Good cages



# Slinging methodology:

- I. 4 leg chain slings will be attached to hook block of the crane.
- II. Hooks of chain slings will then be attached to the designed lifting points of the cage.
- III. Ensure all primary locking and securing mechanisms are being used as per manufacturer's specifications and/or user guides.





Lift Category:		Basic			
Dimensions of load:	Various dimensions: 1.5 t cage typically 1300mm [h] x 1360mm [l] x 1300mm [w] 3 t cage typically 1300mm [h] x 560mm [l] x 1300mm [w]				
Weight of Load	Max payload as per WLL of cage utilised.				
Lifting accessories used with weights of	From hook block: 4 Leg chain slings WLL 8.4 t @ 103kg	WLL x Mode Factor	Resulting SWL		
accessories:	Cage WLL 1.5 t @ 300kg [wcs] Cage WLL 3t @ 500kg [wcs]	4 leg chain slings with 4 legs in use as per design.	_t over all accessories stated		
	Gross weight inc.10% FOS: 2.094 t [ru] for 1.5 t cage & 3.964 t [ru] for 3 t cage	Goods cage being used as per design.	[limited to WLL of goods cage used]		
Ancillary Equipment:	Use close mesh netting to prevent any lightweight materials being blown for within the confines of the cage. When using a net covering ensure the net is secured to the body of the cage.				
Safe lifting considerations:	I. Check condition of the cage, attachment points and any locking mechanism prior to lifting Ensure all primary locking mechanisms on the goods cages are employed as per design use.				
	II. Do not carry materials in the cage that exceed the height of the cage.				
	III. Check underside of the cage for any materials that may have adhered themselves while cage has been stored, especially inside any fork tine points.				
	IV. Always use ALL attachment po	oints when lifting.			

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 34 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01



#### Loads description: Containment accessories - Wheeled bins



## Slinging methodology:


- I. 4 leg chain slings will be attached to hook block of the crane.
- II. Hooks of chain slings will then be attached to the designed lifting points of the wheeled bin.
- III. Use a secured net or designed 'lid' to ensure materials remain inside the bin during transit.

Lift Category:	Basic [empty]		Intermediate [for of empty	The state of the s
Dimensions of load:	Various dimensions: Typically, 760mm [w] x 1460mm [l] x 855mm [h]			
Weight of Load	Typically, max. payload of wheeled bins is 750kg to 1.5 t			
Lifting accessories	From hook block:	w	LL x Mode Factor	Resulting SWL
used with weights of	4 Leg chain slings WLL 8.4 t @ 103kg	_	hain slings with 4 legs	kg over all accessories
accessories:	Wheeled bin @ 108kg [inclusive	in use as	as per design. 	stated.
	of designed lid for some models]		ed bin being used as	[limited to WLL of wheeled bin used]
	Gross weight inc. 10% FOS: _ t [ru]	per design.		_
Ancillary Equipment:	Use proprietary lid (if available for model) or close mesh netting to prevent any lightweight materials being blown from within the confines of the bin.  When using a net covering ensure the net is secured to the body of the bin.			
Safe lifting considerations:			re in place.	
	II. Check condition of the wheeled bin and attachment includes any proprietary coverings used.			
	III. Do not carry materials in t	III. Do not carry materials in the cage that exceed the height of the bin.		
	IV. Always use ALL attachment points when lifting.			
	V. Do not exceed the WLL of the wheeled bin.			

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 35 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01 Dec 2024



### Loads description: Containment accessories – Brick Fork cages



## Slinging methodology:

- I. Single leg chain sling will be attached to hook block of the crane.
- II. Hook of chain sling will then be attached to the designed lifting point of the fork component of the cage.
- III. Fork component will be inserted into pallet and pallet loaded into cage.
- IV. Fork component will then be removed from pallet and lowered into the fork retention pockets.
- V. Mesh gate will be closed and secured as per manufacturer's instructions.

Lift Category:	Basic				
Dimensions of load:	Various dimensions: Typically, 1200mm [w] x 1540mm [l] x 1300mm [h]				
Weight of Load	Typically, max. payload of the cage	es is 2 t			
Lifting accessories	From hook block:	WLL x Mode Factor	Resulting SWL		
used with weights of	Single leg chain sling 6m min WLL 2.5 t @ 10kg [ru]	Single leg chain sling in use			
accessories:	Brick fork cage @ 440kg	as per design.	2 t over all		
	Gross weight inc. 10% FOS: 2.7 t [ru]	Brick fork cage being used as per design.	accessories stated		
Ancillary	Pallet truck requirement at loading/unloading point to load/remove pallet from cage.				
Equipment:	Please note: Not essential but will make the oper	ration more time efficient.	-		
Safe lifting considerations:	I. Check condition of the cag creases that could affect t	ge especially the mesh frontage he integrity of the cage.	for any dents and		
	II. Check underside of the ca	ge in test lift for any adhered ma	aterials		
	III. Do not carry materials in the cage that exceed the height of the cage.	2			
	IV. Ensure that door latches are engaged [1] and that the self-locking latch [2] is secured prior to lifting.				

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 36 of 118 Document No.: Document Rev: Date Approved:



#### Loads description: Containment accessories – Concrete Skips – Bale Arm



## Slinging methodology:

- I. Single leg chain sling will be attached to hook block of the crane.
- II. Hook of chain sling will then be attached to the designed lifting point of the concrete skip.
- III. Once filled, skip will be raised into upright position, tremie pipe secured and arranged so to negate any concrete escaping the pipe.

#### Note:

Best practice is to fold the tremie pipe back over the hanger stanchions located to the rear of the skip.



Lift Category:	Basic				
Dimensions of load:	Various dimensions: Typically, 1780mm [w] x 2720mm [l] x 3500mm [h] for 2000l skip				
Weight of Load	Typically, max. payload of the skips	is 6 t			
Lifting accessories	From hook block:	WLL x Mode Factor	Resulting SWL		
accessories used with weights of accessories:	Single leg chain sling 2m min WLL 8 t @ 15 kg [ru]	Single leg chain sling in use	6 t over all accessories		
	Concrete skip max weight @ 660kg	as per design.			
	Gross weight inc. 10% FOS: 7.35 t [ru]	Concrete skip being used as per design.	stated		
Ancillary Equipment:	For storage on site and to enable a safe washing out procedure, a wash out frame should be employed.				
Safe lifting considerations:	I. When landing skip for stora frame not employed) then end bale arm securing chain is u	ensure the			
	II. Do not use 'greedy' blocks under the frame of the skip when filling. This leads to overfilling of the skip and can lead to unintentional emptying of the skip when raised into the vertical configuration.				
	III. Do not stand under the skip concrete filling point.	on return to			

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 37 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01

Dec 2024

VI.



## Loads description: Containment accessories – Concrete Skips – Bale Arm

# Safe lifting considerations contd.:

- IV. When landing the skip ready to fill, ensure the concrete wagon has pulled forward to allow safe landing and to negate the chance of the hook block of the crane clashing with the hopper at the rear of the skip.
- V. On filling the skip, ensure the concrete being put into the skip is being monitored for oversized lumps of concrete that could cause potential blockage of the tremie pipe

potential blockage of the tremie pipe when emptying at discharge point.

When attaching the hook of the chain sling to the lifting point on the bale arm, check if a suitably sized shackle of sufficient WLL for the load to be carried is required/attached to enable safe attachment.

If you attach the chain sling directly to the aperture in the bale arm there is a chance that hook will not have free movement within the aperture, and this could lead to



overloading of the hook.




Hold point:
Be aware of hand
trap points when
landing the skip into
the 'prone position.

See potential hand trap points in graphic opposite.



## Loads description: Containment accessories – Waste skips with rated/tested lifting points



## Slinging methodology:

- I. 4 leg chain slings will be attached to hook block of the crane.
- II. Hooks of chain sling will then be attached to the designed lifting point of the waste skip.
- III. Ensure the hook of the chain is sitting correctly in the attachment point and that is has free movement.
- IV. Suitable closed mesh netting will now be attached to skip.

Lift Category:		Basic			
Dimensions of load:	Various dimensions but typically 1700mm [w] x 3700mm [l] x 1200mm [h] for an 8-yard skip.				
Weight of Load	Typically, max. payload of the ski	os is 6 t (for dimensions giver	n above]		
Lifting accessories used with weights of	From hook block: 4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor	Resulting SWL		
accessories:	103kg	4 leg chain slings in use as per design.	t [max] over all accessories		
	Waste Skip @ 800kg	as per design.	stated.		
	Gross weight inc. 10% FOS: 7.6 t [ru]	Waste skip being used as per design.	[limited to WLL of waste skip used]		
Ancillary Equipment:	Close mesh netting to be used as cover for the skip to negate the chance of any lightweight materials being 'blown' from within the confines of the skip. When using a net covering ensure the net is secured to the body of the skip				
Safe lifting considerations:	<ul> <li>I. Prior to the skip being allowed on the project the following checks are to be made: <ul> <li>A report of thorough examination is held with site or produced upon arrival to project.</li> <li>Visual checks are made to the base of the skip checking for any cracks to welds, splits, or creases to the base of the skip that would affect the integrity of the containment.</li> <li>Deformation to the lift points and welds around the lifting points.</li> </ul> </li> <li>II. During the test lift check the underside of the cage any adhered materials.</li> <li>III. Do not carry materials in the skip that exceed the height of the cage.</li> <li>IV. Monitor weight of load within the skip, ascertain total load in test lift. If over WLL of skip, put down and do not lift until weight of contents is reduced to WLL limit.</li> </ul>				

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 39 of 118 Document No.: Document Rev: XXXX\_XXXX\_XXXX 01



### Loads description: Containment accessories - Self Discharge Boat skips



## Slinging methodology:

- I. Single leg chain sling will be attached to hook block of the crane.
- II. Hook of chain sling will then be attached to the designed lifting point of the boat skip.
- III. When lowering and raising the skip ensure the 'Dog-bone' mechanism or 'Skip Catch' mechanism[s] are working as anticipated

## Note:

See 'Dog-bone' and 'Skip catch' methodologies detailed in 'Safe Lifting Considerations'

	detailed in Sale Litting Considerations				
Lift Category:	Basic [empty]    Intermediate [when carrying load   emptying]		•		
Dimensions of load:	Various dimensions: Typically for a 2000 l skip 1835mm [w] x 2555mm [l] x 880mm [h]				
Weight of Load	Typically, max. payload of a 2000 ls	skip is 4	t		
Lifting accessories	From hook block:	WI	LL x Mode Factor	Resulting SWL	
used with weights of	Single leg chain sling 2m min WLL 5.3 t @ 15 kg [ru]	_	leg chain sling in use as per design.	t over all	
accessories:	Boat skip @ 540kg  Gross weight inc. 10% FOS: 5.01 t [ru]	Boats	skip being utilised as per design.	accessories stated [limited to WLL of self-discharge skip utilised]	
Ancillary Equipment:	Close mesh netting to be employed as cover for the skip to remove the likelihood of any lightweight materials being 'blown' for within the confines of the skip. When using a net covering ensure the net is secured to the body of the skip.				
Safe lifting considerations:	I. Check attachment point of the integrity of attachmen			ion that could affect	
	II. Do not carry materials in the skip that exceed the height of the skip walls.				
	III. Ensure load placement int Load weight within the ski		•	•	
	IV. Monitor weight of loads be over WLL of skip, put dowr to WLL limit.				
	V. Be aware of hand trap points when using the skip - See potential hand trap points in graphic opposite.				

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 40 of 118 Document No.: Document Rev: Date Approved:



## Loads description: Containment accessories – Self Discharge Boat skips

# Safe lifting considerations contd.:

'Dog-bone' catch:

Self-discharging skips fitted with a lock and release system.

I. The lock is situated at the rear of the skip and engages with the catch fitted to the top of the lifting arm.



II. When the lifting arm is lowered fully, it will engage with the locking system.



III. When next raised, the skip will rise and discharge its load.



IV. When fully lowered a second time, the lifting arm will disengage from the locking system allowing the unit to be raised and manoeuvred to required location on site.



Process Owner: Approved By: Page: Head of Lifting C. Hook Page 41 of 118 Document No.: Document Rev: Date Approved:



## Loads description: Containment accessories – Self Discharge Boat skips

# Safe lifting considerations contd.:

#### Skip-catch:

Self-discharging skips fitted with a hook and catch locking and release system.

V. The hooks are located on both sides of the bale arm and the catches are situated on both sides of the skip body – for clarity



only one side shall be shown in the following methodology.

VI. The hooks engage with the catches as the bale arm is lifted upward and towards the front of the skip and will remain in place until the skip is landed, and the bale arm lowered.




VII. When the bale arm is lowered, ensure the catch does not engage so that the centre of gravity ensures that the skip will then lift in the tipping position.



Process Owner: Approved By: Page: Head of Lifting C. Hook Page 42 of 118 Document No.: Document Rev: Date Approved:





## Slinging methodology:

- 4 leg chain sling will be attached to hook block of the crane. For single point lifting cages, a single leg chain sling is best practice.
- II. Hook[s]of chain sling will then be attached to the designed lifting point of the containment cage. Any unused chain slings to be hung back to the master ring

Lift Category:	Intermediate			
Dimensions of load:	Various dimensions: Single bottle cage typically 600mm [w] x 515mm [l] x 1900mm [h] Multi bottle cage typically 1120mm [w] x 850mm [l] x 2000mm [h]			
Weight of Load	Typically, max. payload of the cage multi bottle carriers	es is 120kg for single bottle carri	ers and 600kg for	
Lifting accessories	From hook block: 4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor	Resulting SWL	
used with weights of accessories:  4 Leg chain slings WLL 8.4 t @ 103kg - For multiple attachment point carriers.  Single leg chain sling WLL 5.3 t @ 10kg [ru] - For single attachment point carriers.	4 leg chain sling with 2 legs in use - WLL of 1 sling x 1.4 = 4.41 t [2no. attachment point carrier] 4 leg chain sling with 4 legs in use – As per design. [4no.	Single bottle cage @ _t over accessories stated [limited to WLL of bottle cage used]		
	Single Gas bottle cage @ 95kg Multi gas bottle cage @ 130kg Gross weight inc. 10% FOS: 350 kg [ru] – Single bottle cage [wcs]	attachment point carrier]  Single leg chain sling in use as per design [Single attachment point carrier]	Multi bottle cage @t over accessories stated [limited to WLL of	
	Gross weight inc. 10% FOS: 917 kg [ru] – Multi bottle cage [wcs]	Gas bottle cage being used as per designed use.	bottle cage used]	
Alternative	Single gas bottle cage - Single leg o	f a multileg chain	111	

## methodology:

sling of sufficient WLL can be used with the unused legs hung back to the master ring.

## Special note:

Some cylinder supply companies do not issue a RoTE for their cylinder carriers.

In these cases, the bottle frame should be slung utilising webbing slings in a 'choke' configuration with the slings being fed through the fork tines insertion points.

Long wear sleeves are to be used on the slings. They should be of sufficient length to protect the slings along all 'pinch' points anticipated.

Slings are to be kept attached to the bottle carrier if multiple lifts of the carrier are required.



Process Owner: Approved By: Page:

Head of Lifting C. Hook Page 43 of 118

Document No.: Document Rev: Date Approved:



#### Loads description: Containment accessories – Gas bottle cages -Single & multi point

# Safe lifting considerations:

- I. Check condition of the cage for any dents, cracks to weld or creases in sheet metal components that could affect the integrity of the cage.
- II. Check underside of the cage in test lift for any adhered materials
- III. Check all securing chains/latches/gates are engaged and working as anticipated prior to lift.

### Please note:

In some cases, the integral lifting points may be too small for a chain hook to be attached to. In this case a suitable sized bow shackle of sufficient WLL will be employed between the hook of the chain sling and the integral lifting point.

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 44 of 118 Document No.: Document Rev: Date Approved:



### Loads description: Containment accessories - Fuel Bowser



Slinging methodology: Direct attachment to lifting points.

- I. 4 leg Chain sling will be attached to hook block of the crane.
- II. Hooks of chain sling will then be attached to the designed lifting point of the fuel bowser.

Slinging methodology: Choke accessories around load

## Chains only:

- 4 leg chain sling will be attached to hook block of the crane.
- II. Hooks of chain sling will then be attached to the bowser in a 'choke' configuration around identified points to the substructure of the bowser.

Lift Category:	Basic [empty ]		Intermediate [cont with	
Dimensions of load:	Various dimensions: Typically - Transcube bowser @ 2000 l capacity 1150mm [w] x 1320mm [h] x 2280mm [l] Typically - Towable bowser @ 950 l capacity 1449 mm [w] x 1498mm [h] x 3175mm [l]			
Weight of Load	Typically: Transcube 2000 l @ un	· ·		
	Typically: Towable Bowser 950 l	@ unladen	450kg / full 1.5 t	
Lifting accessories used	Please note: Following weights are given for	WLL	. x Mode Factor	Resulting SWL
with weights of	a Transcube bowser full.			
accessories:	Chain slings with direct attachment: From hook block >			
	4 Leg chain slings WLL 8.4 t @ 103kg	_	chain sling as per gned use = 8.4 t	_t over accessories stated [limited to WLL
	Bowser WLL _ t @ _ kg			
	Gross weight inc. 10% FOS: 3.203 t [ru]	Bowser as	s per designed use = _ t	of bowser used]
	Chain slings choked: From hook block >	4 leg chain sling with 4 legs in	6.72 t over	
	4 Leg chain slings WLL 8.4t te. @ 103kg	use in a 'choke' configuration = 6.72 t		accessories stated
	Gross weight inc. 10% FOS: 3.203 t [ru]			

Process Owner: Head of Lifting
Approved By: C. Hook
Page: Page 45 of 118

Document No.: XXXX\_XXXX\_XXXX Document Rev: 01

Date Approved:

Dec 2024



#### Loads description: Containment accessories – Fuel Bowser

# Alternative methodology:

Where fuel bowsers have apertures to the bottom of the structure, 'Fork' point etc., webbing slings of a suitable WLL with mode factors considered can be attached around the load in a 'choke' configuration.

Employ wear sleeves to identified pinch points on the structure of the fuel bowser.

Please note:

This methodology can only be used where there is deformation to the direct attachment points rendering them unusable

If size of hook block allows, then the webbing slings can be directly attached.



#### DO NOT OVERCROWD THE BLOCK

# Safe lifting considerations:

- I. Checks to be made with manufacturer regarding bowsers being lifted full. See data plate on the side of the bowser structure for WLL of bowser with contents if applicable.
- II. Ensure all jockey wheels and any outriggers are secure if lifting a wheeled bowser. [Towable Bowser]
- III. Check condition of jockey wheel to ascertain its condition to ensure safe landing of the bowser. [Towable Bowser]
- IV. Check underside of the bowser structure for any loose materials that may have adhered themselves during storage.
- V. Ensure all lockable access doors are closed and secured.
- VI. Check structure of bowser for any loose materials or tools housed within the structure of the bowser.
- VII. Check lifting points for any deformation that could affect integrity of the attachment and that the sizing of will allow a safe attachment with the hook of the chain sling.
- VIII. Ensure that hooks of chain sling move freely within the confines of the attachment point. If not, then use correctly sized shackles of a suitable WLL after mode factor considerations.



#### Loads description: Containment accessories – Jetwash Bowser



Please note:

Chain slings may need to be shortened to suit a level load

## Slinging methodology:

- I. Webbing sling of appropriate length will be fed thru the rear bowser 'tie' down points to form a 'captured cradle' arrangement.
- II. Webbing sling, again of appropriate length, will be attached to lifting eye positioned at the front of the bowser structure via suitably sized bow shackle.
- III. 4 leg chain sling will be attached to the hook block of the crane 3 legs in use so hang the spare leg back to the master ring.
- IV. Attach the hooks of the chain sling to the end loops of the webbing slings

Lift Category:	Basic [empty]		Intermediate [cont with	
Dimensions of load:	Various dimensions: Typically for a 2000 l 1600mm [h] x 4090mm [l] x 1982mm [w]			
Weight of Load	Typically: 2000 l @ unladen 715kg /	′ full 2.8 t		
Lifting accessories used with weights	From hook block >	WLI	x Mode Factor	Resulting SWL
of accessories:	4 Leg chain slings WLL 8.4t @ 103kg	directl	ain sling with 3 legs y attached – as per sign use = 8.4 t	
	Bow shackle Min. WLL 4.25 t @ 2kg		v shackle as per gned use = 4.25 t	4.2 t over accessories
	Webbing slings Min. WLL 3 t of appropriate length @ 7kg [wcs]	poin	ng slings use in a 3- t lift = WLL of one	stated
	Gross weight [full] inc. 10% FOS: 3.21 t [ru]		ied by 1.4 for only 2 ngs used = 4.2 t	
Alternative methodology:	If size of hook block allows, then th	e webbing	slings can be directly	y attached.
	Ensure webbing sling lengths have be slung level.  DO NOT OVERCROWD THE BLOCK	been corre		
Alternative methodology [contd.]:				

Process Owner: Head of Lifting
Approved By: C. Hook
Page: Page 47 of 118

Document No.: XXXX\_XXXX\_XXXX Document Rev: 01
Date Approved: Dec 2024



#### Loads description: Containment accessories – Jetwash Bowser

Where the sub-structure of the bowser allows, a 4 leg chain sling can be employed in a 'choke' configuration around the sub-structure at the front and rear of the bowser.





## Safe lifting considerations:

- I. As far as Is reasonably practicable, lift the bowser empty or full. This is to prevent the centre of gravity changing during the lifting operation.
- II. Ensure all jockey wheels and any outriggers are secure.
- III. Check condition of jockey wheel to ascertain its condition to ensure safe landing of the bowser.
- IV. Check underside of the bowser structure for any loose materials that may have adhered themselves during storage.
- V. Check structure of bowser for any loose materials or tools housed within the structure of the bowser.
- VI. Check lifting points for any deformation that could affect integrity of the attachment and that the sizing of will allow a safe attachment with the hook of the chain sling.
- VII. Check for leaks from engine compartment for fuel powered bowsers.
- VIII. Do not sling around the containment element of the bowser as this can lead to 'splitting' and will affect the integrity of containment.

Date Approved:

XXXX\_XXXX\_XXXX



### Loads description: Containment accessories – FIBC Bags (Fabric bags)



## Slinging methodology: Chain sling

- 4 leg chain sling will be attached to the hook block of the crane
- II. Attach the hooks of the chain sling to the lifting loops of the FIBC situated to each corner of the bag structure

## Slinging methodology: Bulk bag Frame

- 4 leg chain sling will be attached to the hook block of the crane. Single leg in use so hang the unused chains back to the mater ring.
- II. Attach single leg of chain sling to attachment point of frame.
- III. Attach frame to bag as per manufacturer's instructions.

Lift Category:	Dania (fau liftina FIDC in annt	a i a un a un bil	Intermediate [for lift	ing the FIBC not in
	Basic [for lifting FIBC in containment] containment – Low le			ow level only]
Dimensions of load:	Various dimensions: Typically,	900mm [h] x	900mm [l] x 900mm [w	]
Weight of Load	Typically: 1 t for dimensions gi	ven.		
Lifting	From hook block >	WLL	x Mode Factor	Resulting SWL
accessories used with weights of	4 Leg chain slings WLL 8.4 t @ 103kg			-
accessories:	FiBC [Fabric Bag] @ 5 kg	4 leg chai	n sling as per design	
	Bulk bag frame @ 25 kg	use [for sin	use [for single leg use WLL = 2 t]	1 t over
	Gross weight [full] inc. 10% FOS: 1.219 t [ru] – Chain sling with direct attachment	FIBC [Fabric bag] as per design use = 1 t Bulk bag frame as per design use	accessories stated	
	Gross weight [full] inc. 10% FOS: 1.247 t [ru] – Bulk bag frame being utilised			
Alternative methodology:	Bulk Bag lifting frames can be available.	utilised if		00000
	Ensure that the bulk bag frame manufacturer's instructions an sufficient WLL.		er	
	Example: https://cqegroup.com/uk/wp- content/uploads/sites/5/2018/ Lifting-Frame-User-Guide-Issue	2018/02/Bulk-Bag-		
	Please note: All methodologies described he are for Low-Level lifts only.	re and above	T	

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 49 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01

Dec 2024



#### Loads description: Containment accessories – FIBC Bags (Fabric bags)

# Ancillary Equipment:

For lifting across projects, the bags **MUST** be placed in a suitably sized containment accessory of sufficient size to contain the bag c/w an in date RoTE.





# Safe lifting considerations:

I. All bulk bags have been inspected, prior to lifting, to ensure that they have not been damaged during transit to site.

The inspection should be to the same standard as a that for a lifting accessory such as a fabric sling. The inspection should confirm that:

- The bags have been correctly filled and the contents have not shifted during transport.
- There are no abrasions, nicks, tears to the body of the bag or the lifting loops.
- The contents of the bags are not saturated due to rain and therefore possibly overloaded.
- II. Checks are made to ensure the bulk bags can be safely lifted with the lifting equipment and accessories available at site.
- III. The bulk bags are suitable for their intended use at site.

  If bulk material is to be discharged from the bottom of the bag, they should be fitted with a bottom discharge mechanism (spout).

#### Special Note:

Cutting the underside with a knife is not permitted as this could cause shock loading of the crane as well as positioning someone under the load.

- IV. An inspection of the bag(s) is performed to ensure they have not been contaminated with oils, greases, or chemicals during transport.
- V. The bulk bags are lifted in line with instructions issued by the manufacturer.
- VI. At no time are the bulk bags to be lifted over persons even when in a suitably sized containment accessory as above
- VII. When stored on site, they are single stacked only.
- VIII. Single-trip FIBCs should be treated as 'single use' (lifting off a vehicle after delivery), after which they should be destroyed / disposed of as their integrity cannot be guaranteed.
  - IX. After arrival at site, Single-trip FIBCs should not be lifted other than to place them into a suitably sized stillage or certified lifting containment accessory.
  - X. When Bulk bags become damaged, they cannot be lifted. They should be isolated, qua

lifted. They should be isolated, quarantined, and identified as not for lifting. The contents should be placed into a suitably sized stillage or containment accessory as soon as possible. The bag must then be destroyed and disposed of.

It should be assumed that all Single-trip FIBCs, irrespective of content type, are damaged and could fail at any point.

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 50 of 118

Document No.:
Document Rev:

XXXX\_XXXX\_XXXX 01



### Loads description: Formwork components - Ledger frames



## Slinging methodology:

- I. 2no. Webbing slings min. WLL 2t will be attached to the frames in a single wrap 'captured choke' configuration.
- II. 4 leg chain sling will be attached to hook block of the crane. Only 2 legs in use so hang the unused chains back up to the master ring.
- III. Attach the hooks of the chain slings to the loop ends of the webbing slings.

Lift Category:				
Lift Category:		Basic		
Dimensions of load:	Various dimensions: Typically, 1000mm [w] x 1800mm [l] x 50mm [h] – 'Single' frames Typically, 1000mm [w] x 3000mm [l] x 50mm [h] – 'Double' frames			
Weight of Load	Typically, 260 kg for a stack of 25 'S	ingle' frames		
	Typically, 400kg for a stack of 25 'D	Oouble' frames		
Lifting accessories	From hook block > 4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor	Resulting SWL	
used with weights of	103kg	4 leg chain sling with 2 legs in use - WLL of 1 sling x 1.4 =		
accessories:	2no. webbing slings 6m (l) @ 7kg.	4.41 t  2 webbing slings used a set in a choke configuration =  [WLL of one sling multiplied by 1.4] x .8 = 2.24 t	2.24 t over accessories stated	
	Gross weight inc. 10% FOS: 407kg [ru] – 25 no. 'Single' frames			
	Gross weight inc. 10% FOS: 561kg [ru] – 25 no. 'Double' frames			
Alternative methodology:	Chain slings can be used directly around the load(s) in the same configuration as the webbing slings.  If size of hook block allows, then the webbing slings can be directly attached.  DO NOT OVERCROWD THE BLOCK			
Safe lifting considerations:	<ol> <li>Ensure the integrity of the load when landing. Employ banding or a rachet strap around the load.</li> </ol>			
	II. When landing the load use suitably sized timber chocks/spacers to negate having to 'drag' the accessories from the load.			
	III. Land the load on level grouther.	und so that when any securing b	oanding is released	

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 51 of 118 Document No.: Document Rev: Date Approved:



#### Loads description: Formwork components – Primary & secondary Beams



## Slinging methodology:

- 2no. Webbing slings Min. WLL 3 t will be attached to the packs of beams in a double wrap 'choke' configuration.
- II. 4 leg chain sling will be attached to hook block of the crane. Only 2 legs of the chain sling are required so hang the unused chains back up to the master ring.
- III. Attach hooks of chain slings to the lifting loops of the webbing slings.

Lift Category:		Basic			
Dimensions of load:	Various dimensions: Typically, 'Primary' beams @ 500mm [w] x 10m [l] x 1125mm [h] – [5 x 5 pack] Typically, Secondary beams @ 750mm [w] x 7.5m [l] x mm [h] – [10 x 5 pack]				
Weight of Load	Typically, 2 t for a stack of 25 prima Typically, 1.215 t for a stack of 50 so	•			
Lifting accessories	From hook block > 4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor	Resulting SWL		
used with weights of	103kg	4 leg chain sling with 2 legs			
accessories:		in use - WLL of 1 sling x 1.4 = 4.41 t	3.36 t over		
		2 webbing slings used a set	accessories stated		
		in a choke configuration = [WLL of one sling multiplied by 1.4] x .8 = 3.36 t			
Alternative methodology:	Chain slings can be used directly around the load(s) in the same configuration as the webbing slings.  If size of hook block allows, then the webbing slings can be directly attached.  DO NOT OVERCROWD THE BLOCK				
Safe lifting considerations:	Check load for sharp or burred edges on the beams and if necessary, utilise protective sleeves at the recognised pinch points.				
	II. Ensure the integrity of the load when landing. Employ banding or a rachet strap around the load.				
	III. When landing the load use suitably sized timber chocks/spacers to negate having to 'drag' the accessories from the load.				
	IV. Land the load on level gro the load stays together.	und so that when any securing b	panding is released		
	V. Position slings to suit a lev	rel load.			

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 52 of 118

Document No.:
Document Rev:

XXXX\_XXXX\_XXXX 01



## Loads description: – Formwork components – Support legs [outer and inner components]



## Slinging methodology:

- 2no. Webbing slings min. WLL 2 te. will be attached to the packs of beams in a double wrap 'choke' configuration.
- II. 4 leg chain sling will be attached to hook block of the crane. Only 2 legs of the chain sling are required so hang the unused chains back up to the master ring.
- III. Attach hooks of chain slings to the lifting loops of the webbing slings.


		,		
Lift Category:		Basic		
Dimensions of load:	Various dimensions:  Typically, 'Outer' components 1000mm [w] x 4670mm [l] x 1000mm [h] – [5 x 5 pack]  Typically, 'Inner' components 1000mm [w] 1680x mm [l] x 1000mm [h] – [5 x 5 pack]			
Weight of Load	Typically, 566 kg for a stack of 25 'o Typically, 255 kg for a stack of 25 'ii	•		
Lifting accessories	From hook block > 4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor	Resulting SWL	
used with weights of accessories:	103kg	4 leg chain sling with 2 legs in use - WLL of 1 sling x 1.4 = 4.41 t	2.24 t over	
	Gross weight inc. 10% FOS: 744 kg [ru] – 'Outer' components Gross weight inc. 10% FOS: 401 kg [ru] – 'Inner' components	2 webbing slings used a set in a choke configuration = [WLL of one sling multiplied by 1.4] x .8 = 2.24 t	accessories stated	
Alternative methodology:	Chain slings can be used directly around the load(s) in the same configuration as the webbing slings.  If size of hook block allows, then the webbing slings can be directly attached.  DO NOT OVERCROWD THE BLOCK			
Safe lifting considerations:	strap around the load.  II. When landing the load use having to 'drag' the access  III. Land the load on level grouthe load stays together.  IV. Position sling to suit a leve	und so that when any securing l	pacers to negate panding is released	

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 53 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01

Dec 2024



### Loads description: - Formwork components - Panel stacks



## Slinging methodology:

- 2no. webbing slings min. WLL 4 t
   [wcs] will be attached to the packs
   of pans in a double wrap 'choke'
   configuration.
- II. Chain sling[s] will be attached to hook block of the crane. Only 2 legs of the chain sling are required so hang the unused chains back up to the master ring.
- III. Attach hooks of chain slings to the lifting loops of the webbing slings.

Lift Category:	Basic				
Dimensions of load:	Various dimensions but typically:  TOPMAX 2.4m [w] x 5.4m [l] x .720m [h] [Stack 2 pack of 3] – Largest pans TOPEC [Harsco] 1.8m [w] x 1.8m [l] x 1.2m [h] [Stack of 8] – Largest pans PERI (Trio) 2.4m [w] x 3.3m [l] x 1.2m [h] [Stack of 8] – Largest pans				
	Please note: Above weights and dims are given as typical examples through the industry, for other manufacturer's dimensions and weights, check with supplier and adjust accessories to suit net weights calculated.				
Weight of Load	Typically:  TOPMAX @ 2.97 t for a stack of 6 [2 packs of 3]  TOPEC (Harsco) @ 415 kg [ru] for a stack of 8  PERI (Trio) @ 3.184 t for a stack of 8				
Lifting accessories	From hook block > 4 Leg chain slings WLL 8.4 t @ 103kg	WLL x Mode Factor	Resulting SWL		
used with weights of accessories:	2no. webbing slings WLL _ t 10 m [l] [wcs] @ 20kg.	4 leg chain sling with 2 legs in use - WLL of 1 sling x 1.4 = 4.41 t			
	Gross weight inc. 10% FOS: 3.403 t [ru]  - TOPMAX Gross weight inc. 10% FOS: 592 kg [ru]  - TOPEC (Harsco) Gross weight inc. 10% FOS: 3.638 t[ru]  - PERI (Trio)	2 webbing slings used a set in a choke configuration = [WLL of one sling multiplied by 1.4] x .8 = _t	4.48 t over accessories stated		

Process Owner: Head of Lifting Approved By: C. Hook Page: Page 54 of 118

Document No.: XXXX\_XXXX\_XXXX Document Rev: 01



#### Loads description: – Formwork components – Panel stacks

# Alternative methodology:

If size of hook block allows, then the webbing slings can be directly attached.

## DO NOT OVERCROWD THE BLOCK





# Safe lifting considerations:

- I. Ensure the integrity of the load when landing. Employ banding or a rachet strap around the load.
- II. When landing the load use suitably sized timber chocks/spacers to negate having to 'drag' the accessories from the load.
- III. Land the load on level ground so that when any securing banding is released the load stays together.
- IV. Position sling to suit a level load.
- V. Check load for any shorter panels in the stack that aren't captured by banding or the accessories.
- VI. Protection to be used around the webbing sling if required to protect from sharp or burred edges.

#### Single pan movement:

When moving single panels in the horizontal i.e., to make up shutters for walls, columns, and tables etc. some formwork systems will use proprietary lifting accessories i.e., transport bolts.

These lifts should be performed at low level and manufacturers recommended methodologies should be followed.

Do not lift pans as a cradled lift, even for short distances

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 55 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01

ed: Dec 2024



### Loads description: Formwork components - 'Strongback' bundles



## Slinging methodology:

- I. 4 leg chain slings will be attached to hook block of the crane. 2 legs only required so the unused chains will be hung back to the master ring.
- II. 2no. webbing slings min WLL 2t of sufficient length will be attached to the pack of 'strong backs' in a double wrap choke configuration.
- III. Hooks of chain slings will then be attached to the webbing slings.

Lift Category:	Basic		
Dimensions of load:	Various dimensions: Typically, 900mm [w] x 3600 mm [l] x 900mm [h] [pack of 5 x 5]		
Weight of Load	Typically, 1.805 t [pack of 5 x 5]		
Lifting accessories used with	From hook block: 4 Leg chain slings WLL 8.4 t @ 103kg	WLL x Mode Factor 4 leg chain slings with 2 legs	Resulting SWL
weights of accessories:	2no. webbing slings 8 m (l) [wcs] @ 7 kg.	in use - WLL of one leg multiplied by 1.4 = 4.41 t	2.24 t over
	Gross weight inc. 10% FOS: 2.107 t [ru]	2 webbing slings used a set in a choke configuration = [WLL of one sling multiplied by 1.4] x .8 = 2.24 t	accessories stated
Alternative methodology:	Chain sling[s] can be used in a single wrap 'captured choke' configuration through the load by passing the chain sling through the 'holes' in the structure of the bottom row of strong backs – sling to suit a level load.		
	If size of hook block allows, then the webbing slings can be directly attached.		
	DO NOT OVERCROW	D THE BLOCK	
	Single 'Strongback' slinging:		Ţ
	When slinging single 'strong-backs' in the vertical for placement, then checks to be made with manufacturer's instructions as some manufacturers stipulate a proprietary attachment plate or lifting point for this operation.  If none of the above are stipulated, then sling through either the central 'Tie Rod' space in the 'Strongback' structure in a single wrap 'captured choke' configuration.		
	When slinging in the above arrangement ensure you sling under the first strengthening joint as a minimum.		

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 56 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01


proved: Dec 2024



## Loads description: Formwork components – 'Strongback' bundles

# Alternative methodology contd.:

You can also sling through the holes in the structure of the 'Strongback' using the same 'captured choke' configuration. When slinging in these arrangements the schedule must reflect the changes made to weight of load, use of accessory and mode factors employed.



# Safe lifting considerations:


- I. Check underside of pack for any materials that may have adhered themselves during transit or storage.
- II. Securing banding or ratchet strap to be used around the bundle.
- III. Check pack for any shorter lengths of strong backs that have been put in the pack, if found then ensure they are secure. Additional banding or ratchet strap[s] may be required.
- IV. When slinging ensure that all elements of the load are captured by using securing banding around the pack.
- V. Check integrity of landed load after removal of accessories in case of collapse.
- VI. Load slung to suit a level load.
- VII. When lifting strong backs as part of shoring or propping assemblies, ensure that they are free i.e., not bolted to the shutter or any tilt plates / anchors.

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 57 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01

Dec 2024



### Loads description: Formwork - Panels with proprietary clamps in use



## Slinging methodology: - Proprietary clamps

- 4 leg Chain sling[s] will be attached to hook block of the crane. Only 2 legs of the chain sling are required so hang the unused chains back up to the master ring.
- II. Attach 2no. proprietary clamps to the shutter as per manufacturer's instructions.
- III. Attach hooks of the chain slings to the attachment points of the proprietary clamps

Lift Category:	Intermediate				
Dimensions of load:	Various dimensions & weights: See manufacturer's instructions for max. weights and size of shuttering make up for safe lifting.				
Weight of Load	size of shakering make up for safe thang.				
Lifting accessories	From hook block > 4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor	Resulting SWL		
used with weights of	103kg	4 leg chain slings with 2 legs in use - WLL of one leg	3 t over		
accessories:	2no. proprietary clamps WLL 1.5 t @ 20 kg	multiplied by 1.4 = 4.41 t	accessories stated [based on 1.5t		
	Gross weight inc. 10% FOS: _ t [ru]	2 proprietary clamps used as per manufacturer's instructions	clamps being used]		
Alternative methodology:	Single clamp use: Check manufacturer's literature for 'Single' clamp use, the clamps are limited to single pans only.				
	Multi clamp use on 'Box shutters' and larger area shutters  Again, check manufacturer's literature for permissible angles of sling when using multi clamp configurations.				
	Please note: A lifting beam may need to be employed to suit multi clamp use on larger area shutters				
Safe lifting considerations:	I. Do not lift shutters to the with the face of the shutte slab/floor unless manufactinguidance allows.	r to the			
	II. Position the lifting hooks we they cannot slip or secure lifting hooks so that they conslip sideways.	the			
	III. Ensure that the lifting clam of the chain sling.	np attachment ring is seated cor	rectly in the hook		

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 58 of 118 Document No.: Document Rev: Date Approved:



#### Loads description: Formwork – Panels with proprietary clamps in use

# Safe lifting considerations contd.:


Always ensure when removing 'shutter' from formed concrete that you do not use the crane to 'pull' the shutter away. Instead ensure the shutter is released and is clear to lift free. Pulling the 'shutter' from the formed concrete may impose forces on the clamps that are greater than the stated WLL.



# Check the shutter is free to remove – do not use the crane to release the shutter.

- V. Establish weight of shutter prior to lifting for install or removal.
- VI. If relevant ensure all locking pins are in place.
- VII. Slinger to have been familiarised and briefed on the safe use of the proprietary clamp.







- VIII. When landing shutter into the horizontal, ensure suitably sized timbers are placed beneath the shutter to allow safe removal of the clamps.
- IX. Never use the lifting clamps to lift the shutter in the 'Horizontal' across project. The clamps are only designed for 'Vertical' & 'Horizontal to Vertical' use only.
- X. When standing the shutter from horizontal to the vertical monitor the position of the block in relation to the bottom of the wall section so as to keep the wall section from 'swinging' when fully raised.
- XI. Preparation/construction area of the formwork should be as close to the install area as practicable.

#### Special note:


The maximum allowable wind speed for lifting of shutters needs to be assessed on a case by case basis. Consideration should also be given to the route of the lifting operation, noting any zones of wind funnelling / buffeting.

# Additional information:


## Examples of manufacturer sling angles to be employed:

Framax lifting hook [DOKA]:

Determining the correct length of chain



Gang-form with Framed formwork Framax Xlife (example):



Process Owner: Approved By: Page: Head of Lifting C. Hook Page 59 of 118 Document No.:
Document Rev:

XXXX\_XXXX\_XXXX 01




#### Loads description: Formwork – Panels with proprietary clamps in use

## Framax lifting hook [DOKA] contd.

# Additional information: contd.

## Shaft formwork example




## Lifting hook Trio [PERI]:

## Max. crane sling angle = 30°

If the spacing L 1 of the Lifting Hook is smaller than the individual chain length L of the lifting gear, then the crane sling angle is  $\leq 30^{\circ}$ . (Fig. 3)

If the Lifting Hook is used together with the Lifting Gear CombiTRIO, the individual chain length L of the lifting gear is a max. 3.90 m.



## Special note:


Always refer to manufacturer's operating instructions and literature for permissible weights to be lifted & allowable angles of use of the lifting clamps.

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 60 of 118 Document No.: XXXX\_XXXX\_XXXX

Document Rev: 01
Date Approved: Dec 2024



## Loads description: Formwork – Column boxes with proprietary clamp/attachments



# Slinging methodology: -Proprietary clamps/attachments

- 4 leg chain sling will be attached to hook block of the crane. Only 2 legs of the chain sling are required so hang the unused chains back up to the master ring
- II. Attach 2no. proprietary clamps/attachment points to the column shutter as per manufacturer's instructions and to suit a level load.
- III. Attach hooks of the chain slings to the attachment points of the proprietary clamps/integral lifting points

## Please note for clarity:

- Proprietary clamp: A lifting accessory specifically designed for the formwork shuttering – LOLER applies, so RoTE, daily, and weekly check required.
- Proprietary attachment: An integral component of the formwork shuttering structure that enables lifting – PUWER applies, so daily check required.

Lift Category:	Intermediate		
Dimensions of load: Weight of Load	Various dimensions & weights: See manufacturer's instructions for max. weights and dimensions of column boxes permitted to be lifted.		
Lifting accessories	From hook block > 4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor	tor Resulting SWL
used with weights of	103kg	4 leg chain slings with 2 legs in use - WLL of one leg	
accessories:	2no. proprietary clamps WLL _t @ 20 kg	multiplied by 1.4 = 4.41 t	_t over
	Gross weight inc. 10% FOS: _ t [ru]	2 proprietary clamps used as per manufacturer's instructions	
Alternative methodology:	There are various methodologies of lifting column formwork and their associated components.		
	Some manufacturers allow component parts i.e., Access platforms, once attached to the column structure to form lifting points to allow placement /removal of the column box. Others allow the column boxes to be lifted with proprietary support struts attached Please note:  When lifting column boxes with proprietary push-pulls then ensure integrity of the attachment. If 3 <sup>rd</sup> party [not proprietary] push-pulls are being used, then these <b>must</b> be removed prior to lifting the column box. [see following page]		

Process Owner: Head of Lifting
Approved By: C. Hook
Page: Page 61 of 118

Document No.: XXXX\_XXXX\_XXXX Document Rev: 01




## Loads description: Formwork - Column boxes with proprietary clamp/attachments


# Alternative methodology: contd.:

## Examples of manufacturer's components used for lifting:

**DOKA access platform lifting points:** 

#### Moving the platform






The above example shows DOKA guidance on lifting points for their access platform. The first image is for placing the platform, the second image shows the lifting points for removal. Note how the lifting points have changed!

Opposite is composite graphic showing column box being lifted with proprietary support struts.

Lifting with proprietary support struts attached is subject to a TW's review and sign off and only permissible if the project Appointed Person allows.

Lifting with 3<sup>rd</sup> party support struts is forbidden and these must be removed prior to lifting



The platform can stay attached to the formwork throughout this entire operation.

#### PERI access platform lifting points:

## **Placing of Formwork**



Always install the element unit with the concreting platform first.

Locating boards facilitate formwork adjustment.

## Formwork half with concreting platform (placing formwork)

1. Attach 3-sling lifting gear to the crane eyes, lift formwork to a vertical position and then transport to the place of use. (Fig. A3.01)




Fig. A3.01

Above shows guidance provided for lifting column formwork utilising system access platform.

Always refer to manufacturer's literature and guidance when using these methodologies

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 62 of 118

Document No.: Document Rev: XXXX\_XXXX\_XXXX 01



## Loads description: Formwork - Column boxes with proprietary clamp/attachments

# Safe lifting considerations:

- Lifting methodology to follow manufacturer's instructions for safe use.
- If integral attachments are being used, then ensure these are clearly identified and briefed to the lift team.
- Ensure lifting methodology allows a safe landing of the column boxes whether it is being installed around column skeleton or being removed from completed structure.
- Do not 'pull' the column box from the completed structure. Ensure the column is free for removal. Pulling the column box from the formed concrete may impose forces on the clamps/attachment used that are greater than the stated WLL.
- Slinger to have been familiarised and briefed on the safe use of the proprietary clamp/proprietary attachment.



- When standing the shutter from horizontal to the vertical monitor the position of the block in relation to the bottom of the column section so as to keep the wall section from 'swinging' when fully raised.
- Preparation/construction area of the formwork should be as close to the install area as practicable.

#### Special note:

The maximum allowable wind speed for lifting of shuttering columns needs to be assessed on a case by case basis. Consideration should also be given to the route of the lifting operation, noting any zones of wind funnelling / buffeting.



### Loads description: Slab formwork – Tables with proprietary lifting hook - 'C' Hook



#### Please note:

Images above and through the schedule are representational only of a typical methodology

## Slinging methodology:

- I. 4 leg chain slings will be attached to hook block of the crane. 2 legs only required so the unused chains will be hung back to the master ring.
- II. 2 legs of chain sling will be attached to the lifting points on the C Hook.
- III. If applicable the 'forks' of the C-Hook will be adjusted.

## Please note:

Lifting points and, if applicable, 'forks' of the C-Hook will be positioned to suit CoG & sizing of table formation.

- IV. C-Hook arrangement will be raised and placed under the table formation required for lifting.
- V. Table formation will then be attached to C- Hook as per manufacturer's instructions/safe use guide.

Lift Category:	Intermediate		
Dimensions of load:	Various dimensions to suit sizing capacity of proprietary hook – see manufacturer's guidance.		
Weight of Load	Various dimensions to suit WLL of proprietary hook with FOS considered – see manufacturer's guidance.		
Lifting accessories	From hook block: 4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor	Resulting SWL
used with weights of	103kg	4 leg chain slings with 2 legs	
accessories:	C – Hook WLL @ _t	in use - WLL of one leg multiplied by 1.4 = 4.41 t	_t over all accessories stated
	Gross weight inc. 10% FOS: _t [ru]	Proprietary lifting hook, 'C- Hook', as per design use.	decessories stated
Alternative methodology:	Attachment utilising chain sling: Chain sling[s] can be used in a sing wrap 'captured choke' configuration through the load by passing the chasling through cut 'holes' in the top timber structure of the 'table' and 'choked around the primary & secondary beams to suit a level load.	on ain	


Process Owner: Approved By: Page: Head of Lifting C. Hook Page 64 of 118 Document No.: Document Rev: XXXX\_XXXX\_XXXX
01



## Loads description: Slab formwork – Tables with proprietary lifting hook - 'C' Hook

## Safe lifting considerations:

- I. A specific *Risk Assessment* and method statement **must** be authored to suit the lifting of the table formation, from preparation of the arrangement thru to final install and release of C-Hook/accessories.
- II. Care is to be taken in the planning stage when specifying the positioning of not only the lift team members but of the install/removal team as well, through the lifting operation.
- III. Use of proprietary lifting hooks **must** follow the manufacturers safe use guide and operating manual.
- IV. When using proprietary lifting hooks [C- Hooks], ensure the install/removal team, slinger[s] and lifting supervisor[s] are familiarised on the safe use of the hook to ensure correct attachment through the lifting/placing process.
- XIII. When attaching the chain slings to the table formation in the 'choke' configuration, the length of the slings must be sufficient to allow for the chain to be within a 0 to 45 deg. excluded angle.




V. Exclusion and restricted 'zones' must be in place around the immediate install/removal areas and directly beneath the work area. These zones shall be suitably marshalled with appropriate signage. Area of works and timings [where practicable], must be communicated to work force in immediate and

adjacent areas in DABs or specifically held toolbox talks.

#### Please note:

When setting up exclusion and restricted zones around the area beneath the lifting operation, an allowance must be made for falling objects and the anticipated trajectory of fall.



- VI. Prior to lifting table formation ensure that all
  - support 'legs' are secured in the correct manner utilising manufacturer's recommend methodologies of securing.
- VII. If the table formations are to be lifted inclusive of edge protection, then these attachments are subject to a TW 's confirmation to be able to lift.

  These attachments must be included in the weight of the table and assessment of revised balance of the load.



#### Loads description: - Precast concrete elements - Kentledge or 'Kelly' concrete block



#### Slinging methodology - Precast anchor point

- I. Single leg chain sling will be attached to hook block of the crane.
- II. Attach precast lifting accessory min WLL2 t to the cast in anchor point.
- III. Hook of chain sling will then be attached to the anchor point of the concrete block.

#### Slinging methodology - Embedded anchor point

- I. Single leg chain sling will be attached to hook block of the crane.
- II. Hook of chain sling will then be attached to the embedded anchor point of the concrete block.

#### Special note:

Temporary works verification of anchor point required in both above methodologies.

## Slinging methodology – 'Through' the block

- I. 4 leg chain sling will be attached to the hook block of the crane. Only 2 legs in use so hang the unused chains back up to the Master ring.
- II. Feed the chains though the attachment holes in the block and utilise in a single wrap 'captured choke' configuration.

## Slinging methodology – 'Around' the block

- I. 4 leg chain sling will be attached to the hook block of the crane. Only 2 legs in use so hang the unused chains back up to the Master ring.
- II. Feed the chains under the block in single wrap choke configuration.

#### Special note:

Only blocks with 'slinging' notches in the bottom of the block to be lifted this way as the notches form a 'captured choke'.

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 66 of 118 Document No.: XXXX\_XXXX\_XXXX

Document Rev: Date Approved: 01 Dec 2024




Lift Category:	Basic		
Dimensions of load:	Various dimensions: Typically, 800mm [w] x 800mm [l] x 800mm [h]		
Weight of Load	Typically, max. 1800kg for dimensions given		
Lifting accessories used with weights of accessories:	Please note: The following is for the worst-case scenario [wcs] mode factors used in the shown configurations – 'Choked chains around block'  From hook block: 4 Leg chain slings WLL 8.4 t @ 103kg  Gross weight inc. 10% FOS: 2.094 t [ru]	Multi leg chain sling with 2 legs in use in 'choke' configuration – [WLL of one leg multiplied by 1.4] x .8 = 4.48 t	4.48 t over accessories stated
Alternative methodology:	Attachment to anchor points: Single leg of a multi leg chain sling can be used if of sufficient WLL. Hang unused chains back up to the master ring.  Choke attachment: Webbing slings can be employed in the same configuration of the chain slings.  If size of hook block allows, then the webbing slings can be directly attached.  DO NOT OVERCROWD THE BLOCK		
Safe lifting considerations:	<ul> <li>Works check should be per</li> <li>II. Check condition of the lifting immediate area.</li> <li>III. Ensure that any threads are bearing on the insert / block.</li> <li>IV. Check underside of the block.</li> <li>V. If utilising webbing slings, webbing slings in case of slither attachment.</li> <li>VI. When attaching 'through' consufficient length so that the the SWL in the configuration.</li> <li>VII. Check prior to lifting that a</li> </ul>	ck in test lift for any adhered ma ensure there is adequate protec narp edges on the block can affe or 'around' the block, ensure the e angle of the chains doesn't rec	e lifting point. round the  y is fully engaged / aterials. tion of the ect the integrity of e accessories are of quire a reduction of


Dec 2024


Date Approved:



### Loads description: - Precast concrete elements - Legato or 'Lego' blocks







## <u>Slinging methodology – Precast anchor</u> <u>point</u>

- I. Single leg chain sling will be attached to hook block of the crane.
- II. Attach precast lifting accessory min WLL 2 t to the cast in anchor point.
- III. Hook of chain sling will then be attached.
  - a. to the anchor point of the concrete block.

# Slinging methodology – Embedded anchor point

- Single leg chain sling will be attached to hook block of the crane.
- II. Hook of chain sling will then be attached to the anchor point of the concrete block.

#### Special note:

Temporary works verification of anchor point required in both above methodologies.

#### Slinging methodology – 'Around' the block

- 4 leg chain sling will be attached to the hook block of the crane. Only 2 legs in use so hang the unused chains back up to the Master ring.
- II. Feed the chains under the block in single wrap choke configuration.

#### Special note:

Only blocks with 'slinging' notches in the bottom of the block to be lifted this way as the notches form a 'captured choke'.

## **Lift Category:**

## Basic

Process Owner: Head of Lifting
Approved By: C. Hook
Page: Page 68 of 118

Document No.: XXXX\_XXXX\_XXXX
Document Rev: 01
Date Approved: Dec 2024



Loads description: -	Precast concrete ele	ments – Legato or	'Lego' blocks	
Dimensions of load:	Various dimensions: Typically, 800mm [w] x 1600mm [l] x 800mm [h]			
Weight of Load	Typically, max. 1800kg for dimensions given			
Lifting accessories used with weights of	<b>Please note:</b> The following is for the worst-case		WLL x Mode Factor	Resulting SWL
accessories:	sories:  scenario [wcs] mode factors used in the shown configurations – Choked chains around block  Multi leg chain sling with 2	•	4.48 t over	
	From hook block: 4 Leg chain slings WI	LL 8.4t @ 103kg	legs in use in 'choke' configuration – [WLL of one leg multiplied by 1.4]	accessories stated
	Gross weight inc. 10 <sup>th</sup> [ru]	% FOS: 2.094 t	x .8 = 4.48 t	
Alternative methodology:	Attachment to anchor points: Single leg of a multi leg chain sling can be used if of sufficient WLL. Hang unused chains back up to the master ring.  Choke attachment: Webbing slings can be employed in the same configuration of the chain slings.  If size of hook block allows, then the webbing slings can be directly attached.			
Safe lifting			NOT OVERCROWD THE BLO	
considerations:	-	en lifting from a precast or embedded attachment point a Temp orks check should be performed to ensure integrity of the lifting p		
	II. Check cond immediate		point, check for any cracks ar	ound the
	III. Ensure that any threads are clean, and the lifting accessory is fully engaged / bearing on the insert / block.			
	IV. Check underside of the block in test lift for any adhered materials.			
	V. If utilising webbing slings, ensure there is adequate protection of the webbing slings in case of sharp edges on the block can affect the integrity of the attachment.			
	of sufficient	length so that the	around' the block, ensure the angle of the chains doesn't r nfiguration being used.	
	-	v the hook of the cl	attachment holes or notches hain sling to pass through wit	

Date Approved:



## Loads description: – Precast concrete elements – Access chamber rings



## Slinging methodology:

- I. 3no. lifting pins min. WLL 750kg will be attached to the attachment holes located in the side walls of the 'ring' structure.
- II. 4 leg chain sling will be attached to hook block of the crane. Only 3 legs of the chain sling are required so hang the unused chain back up to the master ring.
- III. Attach hooks of chain slings to the attachment eyes of the lifting pins.


Lift Category:	Basic			
Dimensions of load:	Various dimensions: Typically: 1050mm [d] x 1000mm [h]			
Weight of Load	Typically, 900 kg for dimensions give	en		
Lifting accessories	From hook block: 4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor	Resulting SWL	
used with weights of	103kg	4 leg chain sling with 3 legs		
accessories:	Man-hole lifting pins @ 6kg.	in use – As per design use	1.575 t over accessories	
	Gross weight inc. 10% FOS: 1.11 t [ru]	3 Lifting pins min WLL 750kg used as set - WLL of one multiplied by 2.1 = 1.575 t	stated	
Alternative methodology:	Be aware that some Man-hole rings will have a different lifting methodology i.e., 4 chains in use or a different lifting pin than the one stated. In these cases, check documentation of the Man-hole ring and if still unclear consult the manufacturer for guidance.			
Safe lifting considerations:	I. Ensure the lifting pin is corn for the Man-hole ring attact and thickness of the structu	hment holes wall	Pin Diameter	
	II. Use the lifting pin as per mainstruction.	anufacturer's		
	III. During the test lift, check the of the ring for any adhered			
		ne Man-Hole ring for any cracks o upervisor/Appointed Person for		

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 70 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01

Dec 2024



### Loads description: - Precast concrete elements - Access chamber cover slabs



## Slinging methodology:

- I. 4 leg chain sling will be attached to hook block of the crane. Only 3 legs of the chain sling are required so hang the unused chain back up to the master ring.
- II. Attach the hooks of the chain sling directly to the embedded lifting points to the structure of the cover.

Lift Category:	Basic		
Dimensions of load:	Various dimensions: Typically, 1050mm [d] x 675mm [l] x 150mm [h]		
Weight of Load	Typically, 250 kg for dimensions giv	en	
Lifting accessories	From hook block: 4 Leg chain slings WLL 8.4 t @ 103kg  Gross weight inc. 10% FOS: 389 kg [ru] –	WLL x Mode Factor	Resulting SWL
used with weights of accessories:		4 leg chain sling with 3 legs in use – As per design use	8.4 t over accessories stated
Alternative methodology:	Be aware that some access chamber covers will have a different lifting methodology i.e., 4 legs of chain sling in use or a single precast/embedded lifting point. In these cases, check documentation of the access chamber cover and if still unclear consult the manufacturer for guidance.  Please note:  For precast or embedded lifting points a temporary works design check must be made to ensure integrity of the lifting point.		
Safe lifting considerations:	lifting point and has free m point.  II. During the test lift, check the structure of the of the lift.	ooks of the chain sling will fit or ovement within the confines of ne underside of the ring for any cover for any cracks that could	the attachment adhered materials.

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 71 of 118 Document No.: Document Rev: Date Approved:




### Loads description: Precast concrete elements – Vertical Concrete Barriers/Vehicle Crash Barriers (VCB's)









#### Slinging methodology: - 'Around' the VCB

- Attach 4 leg chain sling to the hook block the crane.
- Only 2 legs are required so hang the II. unused chains back up on to the master ring.
- III. Attach the chains around the barrier in a single wrap 'captured' choke configuration.

#### Special note:

Only blocks with 'slinging' notches or fork points in the base of the barrier to be lifted this way as these notches/points form a captured choke.

#### Slinging methodology: - 'Block' Grab

- ١. Attach single leg chain sling to hook block of the crane.
- Attach hook of chain sling to the II. attachment point of the grab.
- III. Utilise the grab on the barrier as per manufacturer's instruction.
- IV. Ensure all component parts of the grab are engaged and check the integrity of load.

#### Special note:

Block grabs are only to be used as a low-level lift for placing.

### Slinging methodology: - Precast anchor point

- ١. Attach single leg chain sling to hook block of the crane.
- II. Attach precast lifting accessory Min WLL 2.5 t. [ must be > than weight of VCB] to the cast in anchor point.
- III. Hook of chain sling will then be attached to the anchor point of the concrete block.

### Slinging methodology: - Embedded anchor point

- I. Attach single leg chain sling to hook block of the crane.
- II. Attach hook of chain sling to the embedded anchor point.

#### Special note:

Temporary works verification of anchor point required in the last 2 methodologies.

Process Owner: Approved By: Page:

Head of Lifting C. Hook Page 72 of 118

Document No.: XXXX\_XXXX\_XXXX 01

Document Rev:

Dec 2024 Date Approved:



Loads description	: Precast concrete elements – Vertic	al Concrete Barriers/Vehicle Cra	sh Barriers (VCB's)		
Lift Category:		Basic			
Dimensions of load:	Various dimensions but typically: 4	50mm [w] x 315 mm [l] x 800mn	ո [h]		
Weight of Load	Typically, 2.5 t for dimensions given				
Lifting accessories used with	Chain sling methodologies  Please note:	WLL x Mode Factor	Resulting SWL		
weights of accessories:	The following is for the worst-case scenario [wcs] mode factors used of the shown configurations utilising chain slings.	4 leg chain sling with 2 legs in use in 'choke'			
	From hook block: 4 Leg chain slings WLL 8.4 t @ 103kg	configuration – [WLL of one leg multiplied by 1.4] x .8 = 4.48 t	4.48 t over accessories stated		
	Gross weight inc. 10% FOS: 2.864 t [ru]				
	Please note: The following is for utilisation of the block grab with worst-case scenario [wcs] weights given for accessories. From hook block: 4 Leg chain slings WLL 8.4 t @ 103kg Block grab Min WLL 3 te. @ 235kg Gross weight inc. 10% FOS: 3.122 t [ru]	4 leg chain sling with 1 leg in use in – WLL of one leg = 4 t  Block grab as per designed use			
Alternative methodology:	Attachment to anchor points & block grab: Single leg of a multi leg chain sling can be used if of sufficient WLL. Hang unused chains back up to the master ring.  Please note:  Some manufacturers use 2no. anchor points to the top of the barrier structure. Adjust methodology, image, and accessory configurations to suit.  Choke attachment: Webbing slings can be employed in the same configuration of the chain slings.  If size of hook block allows, then the webbing slings can be directly attached.  DO NOT OVERCROWD THE BLOCK				
Safe lifting considerations:	When lifting from a precast or embedded attachment point a Temporary Works check should be performed to ensure integrity of the lifting point.  II. Ensure precast lifting attachment[s] are of the correct WLL.				

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 73 of 118

Document No.: Document Rev: Date Approved:



### Loads description: Precast concrete elements – Vertical Concrete Barriers/Vehicle Crash Barriers (VCB's)

Safe lifting considerations	III.	Check condition of the lifting point, check for any cracks around the immediate area.
contd.	IV.	Check underside of the barrier in test lift for any adhered materials.
	V.	If utilising webbing slings, ensure there is adequate protection of the webbing slings in case of sharp edges on the barrier that can affect the integrity of the attachment.
	VI.	When attaching 'around' the barrier, ensure the accessories are of sufficient length so that the angle of the chains doesn't require a reduction of the SWL in the configuration being used.
	VII.	Check prior to lifting that any attachment 'notches' are of sufficient size to allow the hook of the chain sling to pass through without using excessive force.
	VIII.	When using hydraulic grabs these should be of low-level lifts only. If required to lift over shoulder height then these operations are subject to a specific risk

marshalled, and sign posted.


assessment being authored and should be performed in a sterile area i.e., restricted zones with physically barriered exclusion zones that are suitably

Process Owner: Head of Lifting
Approved By: C. Hook
Page: Page 74 of 118

Document No.: XXXX\_XXXX\_XXXX
Document Rev: 01
Date Approved: Dec 2024



#### Loads description: Precast concrete elements - Stair units



#### Slinging methodology:

Direct attachment of chain slings to cast in anchor points...

- I. Lifting anchors shall be attached to the cast in lifting points as per manufacturer's instructions.
- II. 4 leg chain sling will then be attached to the hook block of the crane.
- III. Chain-sling will then be arranged to suit 'placement' of stair unit.
- IV. Hooks of chain sling will then be attached to the Lifting anchors

Please note:

Configuration of chains to be identified in the lift plan and not 'worked' out at point of lift.

**Lift Category:** 


### Intermediate[as a minimum]

Complex [dependant on localised parameters and hazards]



Various dimensions: When stating sizing of the stairs give the size as per 'Install' configuration

See example opposite



#### Weight of Load

### Various weights over different designs

### Lifting accessories used with weights of accessories:

From hook block > 4 Leg chain slings WLL 8.4 t @ 103kg

Precast attachment point anchors Min. WLL to suit weight of stairs as per design.

Additional accessories Min. WLL to suit methodology of use in the lifting arrangement.

Gross weight inc. 10% FOS: \_t [ru]

#### WLL x Mode Factor

4 leg chain slings per designed use

Precast attachment anchors WLL as per TW design attending to stair weight

Additional accessory [description here] Min. WLL

#### **Resulting SWL**

\_t over
accessories stated
will be to suit
design weight of
stair units with
mode factors
considered for
required use in
the methodology.

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 75 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01



#### Loads description: Precast concrete elements – Stair units

### Alternative methodology:

Additional accessories i.e., chain blocks, lever hoists can be employed to assist in manipulating the load orientation prior to install.

When using these 'additional' accessories the WLL of ALL accessories should be assessed to factor in all considered mode factors.

Ensure that the 'additional' accessories are used within their own working parameters by referring to the manufacturer's instructions as evidence they are being used as intended




Example opposite shows a lever hoist being used on the 'upper' section of stairs to aid configuring the stairs into an 'install' orientation.

### Safe lifting considerations:

- I. A specific *risk assessment* and method statement **must** be authored to suit the lifting of the stair unit from preparation of the arrangement thru to final install and release of accessories.
- II. Care is to be taken in the planning stage when attending to the positioning of not only the lift team members but of the installation team as well, through the lifting operation.
- III. Stair unit installation historically takes place in restrictive areas with limited identifiable 'Safe Spaces'.
  Safe 'emergency' egress must be identified in the planning stage and prior to submittal.
- IV. When lifting 'blind' a robust communication strategy **must** be in place.
- V. Preparation area of the lifting arrangement should be as close to the install area as practicable. A lifting corridor should be planned and briefed to all the work force in the localised and adjacent work areas.
- VI. Any additional 'furniture' to the stair units i.e., handrails etc. are to be included in the weight of the load and subject to a TW review & confirmation of permissible attachment.
- VII. Seek advice from manufacturers guidance and literature for the safe use and implementation of the precast lifting accessories. This will include [but not exhaustive of]:

Following graphics are typical examples.

Safe and correct attachment:



Process Owner: Approved By: Page: Head of Lifting C. Hook Page 76 of 118 Document No.: Document Rev: Date Approved:



#### Loads description: Precast concrete elements - Stair units


## Safe lifting considerations contd.:

### Angles of use:

### 'Wear' limits of the anchors:

#### ig is .

2. Lifting
The ring clutch can be subjected to loads in any direction (do not exceed the load limits of the anchors!). Angled pull of up to 60° due to the use of a spreader is permissible.



		Wear limits fo	r the lip thickne	ess "m" and hole	e size for "h" [m	m]	
Load class	1.0 to 1.3	1.5 to 2.5	3.0 to 5.0	6.0 to 10.0	12.0 to 20.0	32.0	45.0
m <sub>min</sub>	5.5	6.0	8.0	12.0	18.0	24.0	24.0
h <sub>max</sub>	13.0	18,0	24.5	32.5	47.5	58,0	58,0
	Wear	limits for minim	um link diamet	er "g" and chair	n link elongation	"f" [mm]	
gmin	14.0	17.5	28.0	36.0	56.0	80.0	85.0
f <sub>min</sub>	10.5	12.5	18.5	26.0	36.0	40.0	48.5
1 /6/					F 1 4	1 1700	
	= [				Cross section when <b>new</b>	Cross section after period of use	Beading should no be remove or ground down

VIII. When using additional accessories, ensure the attachment for 'in line' use is realised using appropriate attachment accessories.



Process Owner: Approved By: Page: Head of Lifting C. Hook Page 77 of 118 Document No.: XXXX\_XXXX\_XXXX Document Rev: 01

Document Rev: 01
Date Approved: Dec 2024



### Loads description: Precast concrete elements – ILU's [Intermediate 'landing' units] / Capping slab units



### Slinging methodology:

- Lifting anchors shall be attached to the cast in lifting points as per manufacturer's instructions.
- II. 4 leg chain sling will then be attached to the hook block of the crane.
- III. Hooks of chain sling will then be attached to the Lifting anchors

Lift Category:	Intermediate [as minimum]	1	Complex [dependant on local parameters and hazards]			
Dimensions of load:	Various dimensions over assorted designs					
Weight of Load	Various weights over assorted designs					
Lifting accessories	From hook block > 4 Leg chain slings WLL 8.4 t @	W	LL x Mode Factor	Resulting SWL		
used with weights of	103kg			_t accessories stated		
accessories:	Precast attachment point anchors Min. WLL to suit weight	4 lo	eg chain slings per designed use	[This will be to suit design weight		
	of units as per design.	Precast attachment anchors WLL as per TW design attending to unit weight		of the units with mode factors considered for required use in the methodology]		
	Gross weight inc. 10% FOS: _t [ru]					
Safe lifting considerations:	I. A specific risk assessment and method statement <b>must</b> be authored to suit the lifting of the landing/capping slab unit from preparation of the arrangement through to final install and release of accessories.					
	II. Care is to be taken in the planning stage when attending to the positioning of not only the lift team members but of the installation team as well, through the lifting operation.					
	III. Intermediate 'landing' units. These lifts historically take place in restrictive areas with limited identifiable 'Safe Spaces'. Safe 'emergency' egress <b>must</b> be identified in the planning stage.					
	IV. Capping slabs. Historically performed at height, so again, safe 'emergency' egress and 'safe spaces' must be identified, as well as working from height management, in the planning stage.					
	V. When lifting 'blind', which isn't uncommon especially in the place landing sections, then a robust communication strategy <b>must</b> be					
Dracace Owner	Hood of Lifting		Dogument No.	VVVV VVVV VVVV		

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 78 of 118 Document No.: Document Rev: Date Approved:




### Loads description: Precast concrete elements – ILU's [Intermediate 'landing' units] / Capping slab units

### Safe lifting considerations contd.:

- VI. Preparation area of the lifting arrangement should be as close to the install area as practicable. A lifting corridor should be planned and briefed to all the work force in the localised and adjacent work areas.
- VII. Any additional 'furniture' to units i.e., handrails etc. are to be included in the weight of the load and subject to a TW review & confirmation of permissible attachment.
- VIII. Seek advice from manufacturer's guidance and literature for the safe use and implementation of the precast lifting accessories. This will include [but not exhaustive of]:

Following graphics are typical examples.


Safe and correct attachment: example graphic below



#### Angles of use:

#### 'Wear' limits of the anchors:

The ring clutch can be subjected to loads in any direction (do not exceed the load limits of the anchors!). Angled pull of up to 60° due to the use of a



#### Wear limits for the lip thickness "m" and hole size for "h" [mm] 1.5 to 2.5 3.0 to 5.0 6.0 to 10.0 12.0 to 20.0 24.0 24.0 13.0 18.0 24.5 32.5 47.5 58.0 58.0 Wear limits for minimum link diame ter "g" and chain link elongation [mm] 14.0 17.5 28.0 36.0 56.0 80.0 85.0 ① It is prohibited to re-bend any element damaged by mis-use. De-commission the universal head lifting link if there is any significant bending.

Process Owner: Approved By: Page:


Head of Lifting C. Hook Page 79 of 118


Document No.: Document Rev:

Date Approved:



### Loads description: Precast concrete elements – Concrete drainage pipes [Single]





### Slinging methodology: - Choked slings

- I. 4 leg chain slings will be attached to hook block of the crane. 2 legs in use so hang the unused chains back to the master ring.
- II. 2no. webbing slings min WLL 3t of sufficient length will be attached to the stillage in a double wrap – choke configuration.
- III. Hooks of chain slings will then be attached to the webbing slings.

### Slinging methodology: - Pipe lifter

- I. Pipe lifter chain will be attached to hook block of the crane.
- II. Lifting hook attachments will now be placed at the pipe ends as per manufacturer's instructions.

#### Please note:

Pipe lifting chain set is **only** to be used as a low-level lifting accessory for placing.

Lift Category:	Basic				
Dimensions of load:	Various dimensions: Typically: 1080mm [d] x 2500mm [l]				
Weight of Load	Typically, 2.057 t for dimensions given				
Lifting accessories	Webbing Sling methodology:	WLL x Mode Factor	Resulting SWL		
used with weights of accessories:	From hook block > 4 Leg chain slings WLL 8.4 t @ 103kg	4 leg chain slings with 2 legs in use - WLL of one leg multiplied by 1.4 = 4.41 t	3.36 t over		
	2no webbing slings 8m [l] @ 7kg  Gross weight inc. 10% FOS: 2.384 t [ru]	2 webbing slings used a set in a choke configuration = [WLL of one sling multiplied by 1.4] x .8 = 3.36 t	accessories stated		
	Pipe Lifting Chain Sling methodology:  From hook block > Pipe Lifting Chain Sling WLL 2.5 t @ 60kg  Gross weight inc. 10% FOS: 2.33 t [ru]	Pipe lifting chain sling as per designed use	2.5 t over accessories stated		

Process Owner: Head of Lifting
Approved By: C. Hook
Page: Page 80 of 118

Document No.: XXXX\_XXXX\_XXXX Document Rev: 01

Dec 2024

Date Approved:



#### Loads description: Precast concrete elements – Concrete drainage pipes [Single]

### Alternative methodology:

Webbing Sling methodology:

If size of hook block allows, then the webbing slings can be directly attached.

#### DO NOT OVERCROWD THE BLOCK

Pipe Lifting Chain Sling methodology:






If the master ring of the pipe lifting chain set does not have a correct seating arrangement to the 'bowl 'of the hook of the crane, then a suitably sized shackle of sufficient WLL can be used between hook block of crane and master ring.

### Safe lifting considerations:

- I. Ensure the pipe lifting chain sling master ring is of sufficient size to attach to the 'bowl' of the hook of the crane.
- II. When using pipe lifting chain sets, these should be of low-level lifts only. If required to lift over shoulder height then these operations are subject to a specific risk assessment being authored and should be performed in a sterile area i.e., restricted zones with physically barriered exclusion zones that are suitably marshalled, and sign posted.
- III. All lifts with pipe lifting chain sets are to be of a slow and steady manner.
- IV. During the test lift check underside of the pipe for any adhered materials.
- V. Place accessories to suit a level load.
- VI. Check pipe for any cracks or signs of damage that could affect the integrity of the pipe.
- VII. When landing the pipe for storage ensure that suitably sized timbers or spacers chocks are employed to negate having to drag accessories from under the load.
- VIII. Employ stop blocks or similar to base/bottom the load to stop any rolling after accessories have been removed.



### Loads description: Clay pipe [drainage] - Bundle



### Slinging methodology:

- I. 4 leg chain slings will be attached to hook block of the crane. 2 legs in use so hang the unused chains back to the master ring.
- II. 2no. webbing slings min WLL 2 t of sufficient length will be attached to the stillage in a double wrap choke configuration.
- III. Hooks of chain slings will then be attached to the webbing slings.

Lift Category:	Basic					
Dimensions of load:	Various dimensions: Typically, 1000mm [w] x 1000mm [h] x 2000mm [l] for pack of 9 plain ended pipes. 300mm in diameter @ 2000mm in length @ 78.3kg p/m [ru]					
Weight of Load	Typically, 1.41 t [ru] for dimensions	and specification given above				
Lifting accessories	From hook block > 4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor	Resulting SWL			
used with weights of	103kg	4 leg chain slings with 2 legs in use - WLL of one leg				
accessories:	2no webbing slings 8m [l] @ 7kg	multiplied by 1.4 = 4.41 t	2.24 t over			
	Gross weight inc. 10% FOS: _t 1.672 t	2 webbing slings used a set in a choke configuration = [WLL of one sling multiplied by 1.4] x .8 = 2.24 t	accessories stated			
Alternative methodology:	If size of hook block allows, then th slings can be directly attached. <b>DO NOT OVERCROWI</b>					
Safe lifting considerations:	<ol> <li>Check underside of pack for during transit or storage.</li> </ol>	or any materials that may have a	adhered themselves			
	II. Securing banding or ratche	et strap to be used around the b	oundle.			
	III. Check pack for any shorter lengths of pipe that have been put in the pack, if found then ensure they are secure. Additional banding or ratchet strap[s] may be required.					
	IV. When slinging ensure that securing banding around t	all elements of the load are cap he pack.	tured by using			
	V. Check integrity of landed local	oad after removal of accessories	s in case of			
	VI. Load slung to suit a level lo	oad.				

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 82 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01

contd.:



Loads description: Clay pipe [drainage] - Bundle				
Safe lifting	VII.	Ensure timber packing is used between levels of pipes to aid integrity &		
considerations		stability of load when landed.		

VIII. After the test lift, lower the load to the floor without releasing the weight of the load and, if required, retighten the ratchet strap to ensure integrity of the

encasement of the load

Process Owner: Head of Lifting Approved By: C. Hook Page: Page 83 of 118

Document No.: XXXX\_XXXX\_XXXX
Document Rev: 01
Date Approved: Dec 2024



### Loads description: Steel pipe [drainage] - Bundle



Process Owner:

Approved By:

Page:

Head of Lifting

Page 84 of 118

C. Hook

### Slinging methodology:

- 4 leg chain slings will be attached to hook block of the crane. 2 legs in use so hang the unused chains back to the master ring.
- II. 2no. endless webbing slings min WLL 2t of sufficient length will be attached to the stillage in a double wrap choke configuration.
- III. Hooks of chain slings will then be attached to the webbing slings.

Lift Category:	Basic				
Dimensions of load:	Various dimension: Typically, 440mm [w] x 440mm [h] x 3000mm [l] for a pack of 16 drainage pipes - Single pipe @ 110mm diameter, 6mm wall thickness and 3000mm in length @ 16.17kg p/m [based on a standard drainage pipe cast in raft slabs]				
Weight of Load	Typically, 777 kg [ru] for specificati	on and dimensions above			
Lifting accessories	From hook block > 4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor	Resulting SWL		
used with	103kg	4 leg chain slings with 2 legs			
weights of accessories:	2no webbing slings 8m [l] @ 7kg	in use - WLL of one leg multiplied by 1.4 = 4.41 t	2.24 t over		
	Gross weight inc. 10% FOS: 976 kg [ru]	2 webbing slings used a set in a choke configuration = [WLL of one sling multiplied by 1.4] x .8 = 2.24 t	accessories stated		
Alternative methodology:	If size of hook block allows, then the webbing slings can be directly attached.  DO NOT OVERCROWD THE BLOCK				
Safe lifting considerations:	I. Best practice is to use endless round slings when slinging steel tubes, the slings encase and grip the load better than flatwoven. If using flatwoven, ensure it exerts a force uniformly on to the outside of the bundle, ensuring all items within cannot move around or fall out.				
	II. Check underside of bundle themselves during transit	e for any materials that may hav or storage.	e adhered		
Cafa lifeina	III. Securing banding or ratch	et strap to be used around the b	undle.		
Safe lifting considerations contd.:	IV. Check bundle for any shorter lengths of pipe that have been put in the pack, if found then ensure they are secure. Additional banding or ratchet strap[s] may be required.				
	V. When slinging ensure that all elements of the load are captured by using securing banding around the bundle.				
	VI. Check integrity of landed l	oad after removal of accessories	s in case of collapse.		

Document No.:

Document Rev:

Date Approved:

XXXX\_XXXXX\_XXXX

01



### Loads description: Steel pipe [drainage] - Bundle

- VII. Load slung to suit a level load.
- VIII. Ensure timber packing is used between levels of pipes to aid integrity & stability of load when landed.
- IX. After the test lift lower the load to the floor without releasing the weight of the load and, if required, retighten the ratchet strap to ensure integrity of the encasement of the load

Process Owner: Head of Lifting Approved By: C. Hook Page: Page 85 of 118

Document No.: XXXX\_XXXX\_XXXX Document Rev: 01 Date Approved: Dec 2024



### Loads description: Scaffolding tubes – Stillages 5' to 10' only



### Note: Image is representational only and not to scale for length of scaffold tubes

Process Owner:

Approved By:

Page:

Head of Lifting

Page 86 of 118

C. Hook

### Slinging methodology:

- I. 4 leg chain slings will be attached to hook block of the crane. 2 legs in use so hang the unused chains back to the master ring.
- II. 2no. webbing slings min WLL 2t of sufficient length will be attached to the stillage in a double wrap choke configuration.
- III. Hooks of chain slings will then be attached to the webbing slings.

Lift Category:	Basic				
Dimensions of load:	Various dimensions but typically: 1020mm [w] x 600mm [h] x Max. 10' [l]				
Weight of Load	Typically, 1 t for a full stillage [base	ed on standard stillage WLL]			
Lifting accessories	From hook block > 4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor	Resulting SWL		
used with weights of	103kg	4 leg chain slings with 2 legs in use - WLL of one leg			
accessories:	2no webbing slings 8m [l] @ 7kg	multiplied by 1.4 = 4.41 t	2.24 t over		
	Gross weight inc. 10% FOS: 1.23 t [ru]	2 webbing slings used a set in a choke configuration = [WLL of one sling multiplied by 1.4] x .8 = 2.24 t	accessories stated		
Alternative methodology:	If size of hook block allows, then the webbing slings can be directly attached.  DO NOT OVERCROWD THE BLOCK				
Safe lifting considerations:	I. Sling positions to suit a le	vel load.			
considerations:	II. Check condition of the stil	llage prior to lifting.			
	III. Check integrity of the feet	to ensure the stillage doesn't co	ollapse on landing.		
	IV. Splits, dents, and creases that could affect the integrity of the structure when slinging?				
	•	ne stillage to just make sure that nselves to the inside of the feet.	stones or mud		
		of the legs for any small objects, ould fall out once stillage is raise	•		

Document No.:

Document Rev:

Date Approved:

XXXX\_XXXXX\_XXXX

01



Loads description: Scaffolding tubes – Stillages 5' to 10' only						
		VII. Ensure that all lengths of the tubes are of similar length and remove any short lengths prior to lifting.				
Safe lifting considerations		/III. Ensure that there are no loose tubes that can slide out of the middle of the bundle during the lifting operation.				
IX. Ratchet strap <b>must</b> be employed around the stillage, so it encases of tubes. After the test lift, lower the stillage to the floor without reweight of the load and, if required, retighten the ratchet strap to exintegrity of the encasement of the load.					ithout releasing the	
Additional	D-f::	Tube length [m/foot]				
information:	Reference weights:	1.50/52			2.040 /102	
	4 . 1 [1 ]	1.52m/5'	1.829m/6'	2.439m/8'	3.048m/10'	
	1no. tube [kg]	6.84 kg	8.24 kg [ru]	11 kg [ru]	13.8 kg [ru]	
	Bundle of 61no. [kg]	418 kg [ru]	503 kg [ru]	671 kg	842 kg [ru]	
	All weights based on 4.5kg per metre and rounded up thru each calculation.					
	For example: 10' scaffold tube @ 3.048m so3.048 x 4.5 = 13.716 ru. to 13.8 x 61 (tubes) = 841.8 kg ru. to 842kg					

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 87 of 118

Document No.: Document Rev: Date Approved:



#### Loads description: Scaffold tubes – Bundles 7' to 21' only



### Slinging methodology:

- . 4 leg chain slings will be attached to hook block of the crane. 2 legs in use so hang the unused chains back to the master ring.
- II. 2no. webbing slings min WLL 2 t of sufficient length will be attached to the bundle in a double wrap choke configuration.
- III. Hooks of chain slings will then be attached to the webbing slings.

Lift Category:	Basic				
Dimensions of load:	Various dimensions: Typically, (for a bundle of 61 x 21' tubes) 435 mm [w] x 6410 mm [21'] [l] x 435 mm [h]				
Weight of Load	Typically, 1.72 t [wcs] for a pack of	61 x 21' tubes			
Lifting accessories	From hook block > 4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor	Resulting SWL		
used with weights of accessories:	103kg  2no. webbing slings @ min 3.5m (l) @ 5kg	4 leg chain slings with 2 legs in use - WLL of one leg multiplied by 1.4 = 4.41 t	2.24 t over		
	Gross weight inc. 10% FOS: 2.1 t [ru]	2 webbing slings used a set in a choke configuration = [WLL of one sling multiplied by 1.4] x .8 = 2.24 t	accessories stated		
Alternative methodology:	If size of hook block allows, then the webbing slings can be directly attached.  DO NOT OVERCROWD THE BLOCK				
Safe lifting considerations:	<ul> <li>I. Best practice is to use endless round slings when slinging scaffold tubes, the slings encase and grip the load better than flatwoven.  If using flatwoven, ensure it exerts a force uniformly on to the outside of the bundle, ensuring all items within cannot move around or fall out.</li> <li>II. When slinging the scaffold tubes with webbing slings, keep the length of the slings down to a minimum. With other bundled loads, longer slings are required to enable a double wrap. With scaffold tubes, the circumference of a manufacturer's bundle of 61 tubes is approx. 1.74m so to enable a double wrap only 3.5m of sling is required. Keeping the slings to a minimum will help negate the swing of the load.</li> </ul>				

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 88 of 118 Document No.: Document Rev: Date Approved:



#### Loads description: Scaffold tubes – Bundles 7' to 21' only

## Safe lifting considerations contd.

Special note:

When directly attaching webbing slings to the block, the length of the slings must be sufficient to keep within a 0 to 45 deg. excluded angle.



- III. Ensure that all lengths of the tubes are of similar length and remove any short lengths prior to lifting.
- IV. Place slings to suit a level load.
- V. Securing banding or ratchet strap to be used around the bundle.

### Additional information:

Reference weights:	Tube length [m/foot]					
Ü	1.52m/5'	1.829m/6'	2.439m/8'	3.048m/10'		
1no. tube [kg]	6.84 kg	8.24 kg [ru]	11 kg [ru]	13.8 kg [ru]		
Bundle of 61no. [kg]	418 kg [ru]	503 kg [ru]	671 kg	842 kg [ru]		

All weights based on 4.5kg per metre and rounded up thru each calculation.

For example:

10' scaffold tube @ 3.048m so... 3.048 x 4.5 = 13.716 ru. to 13.8 x 61 (tubes) = 841.8 kg ru. to 842kg

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 89 of 118 Document No.: Document Rev: Date Approved:



### Loads description: Site plant – Mobile tower lights




### Slinging methodology:

- I. Configure the lighting set mast for lifting as per manufacturer's instructions.
- II. Attach single leg chain sling to hook block of the crane.
- III. Attach hook of chain sling to the identified lifting point of the anchor point.

Please note: Lifting points are usually identified by the mark shown opposite

Where lifting points are not marked then consult the operating manual – see opposite for typical non - marked lifting point.





Lift Category:	Basic				
Dimensions of load:	Various dimensions but typically: 1380mm [w] x 2420mm [h] x 2320mm [l]				
Weight of Load	Typically, 1 t for dimensions given				
Lifting accessories	From hook block > WLL x Mode Factor Resulting				
used with weights of accessories:	25 kg	Single leg chain sling as per designed use	2 t over accessories stated		
Alternative methodology:	Single leg of a multileg chain sling of sufficient WLL can be used with the unused legs hung back to the master ring.				
Safe lifting considerations:	<ul> <li>I. Prior to lifting check all jockey wheels and outriggers [If applicable] are secure.</li> <li>II. Check housing of the lighting set for any loose materials or tools that could be stored within.</li> <li>III. Check engine compartment for oil or fuel leaks</li> <li>IV. Check mast section is locked and configured for lifting. Do not lift without the mast section detracted or suitably stowed as per manufacturer's instructions</li> </ul>				

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 90 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01



### Loads description: Site plant – Mobile tower lights

- V. Check jockey wheel condition to allow safe landing of the lighting set
- VI. Check glass on light frames to ensure there are no cracks that could affect the integrity of the housing of the glass once lifted.
- VII. Check integrity of the lifting point for deformities.



Process Owner: Approved By: Page: Head of Lifting

Page 91 of 118

C. Hook

Document No.: Document Rev: Date Approved:



#### Loads description: Site plant - Compressors



### Slinging methodology:

- I. Attach single leg chain sling to hook block of the crane.
- II. Attach hook of chain sling to the integral lifting point of the compressor anchor point.

Lift Category:	Basic				
Dimensions of load:	Various dimensions: Typically, 1700mm [w] x 1545mm [h] x 3565mm [l] for 4 tool compressor				
Weight of Load	Typically, 1.3 t for 4 tool compresso	r			
Lifting accessories	From hook block > WLL x Mode Factor Resulting SV				
used with weights of accessories:	vith 25kg	Single leg chain sling as per designed use	2 t over accessories stated		
Alternative methodology:	Single leg of a multileg chain sling of sufficient WLL can be used with the unused legs hung back to the master ring.  Special note:  Where the lifting point appears to be corroded / unsound for lifting, consult the lifting supervisor / appointed person to assess lifting with chains / slings around the chassis.				
Safe lifting considerations:	<ul> <li>II. Check jockey wheel conditi the compressor.</li> <li>III. Check housing of the lighting materials or tools that coul</li> <li>IV. Check compressor for oil or compressor once landed satisfies.</li> <li>V. Check integrity of the lifting</li> <li>VI. Ensure compressor is switce</li> </ul>	<ol> <li>Prior to lifting check jockey wheel is secure.</li> <li>Check jockey wheel condition to allow safe landing of the compressor.</li> <li>Check housing of the lighting set for any loose materials or tools that could be stored within.</li> <li>Check compressor for oil or fuel leaks- Utilize a 'plant nappy' under the compressor once landed safely.</li> <li>Check integrity of the lifting point for deformities.</li> <li>Ensure compressor is switched off.</li> </ol>			

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 92 of 118

Document No.: Document Rev: Date Approved:



### Loads description: Site plant – Welding set generator



### Slinging methodology:

- I. Attach single leg chain sling to hook block of the crane.
- II. Attach hook of chain sling to the integral lifting point of the compressor anchor point.

Lift Category:		Basic	
Dimensions of load:	Various dimensions: Typically, 785 mm [w] x 890 mm [h] x 1270 mm [l]		
Weight of Load	Typically, 250 kg for dimensions given		
Lifting accessories used with weights of accessories:	From hook block > Single leg chain sling WLL 2 t @ 25kg  Gross weight inc. 10% FOS: 303kg [ru]	WLL x Mode Factor  Single leg chain sling as per designed use	Resulting SWL  2 t over accessories stated
Alternative methodology:	Single leg of a multileg chain sling of sufficient WLL can be used with the unused legs hung back to the master ring.  Special note:  Where the lifting point appears to be corroded / unsound for lifting, consult the lifting supervisor / appointed person to assess lifting with chains / slings around the chassis.		
Safe lifting considerations:	<ul> <li>I. Check integrity of the lifting deformities.</li> <li>II. Check that the hook of the into the lifting point, if nee of a suitable WLL can be enthe hook of the chain sling attachment point.</li> <li>III. Ensure that all compartme that any cables are either stremoved prior to lifting.</li> <li>IV. Check generator for oil or figenerator once landed safe</li> <li>V. Check generator is switched</li> </ul>	chain sling fits ded a bow shackle nployed between and the ents are secure and secured or fuel leaks – Utilize a 'plant nappely.	y' under the

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 93 of 118

Document No.:
Document Rev:

XXXX\_XXXX\_XXXX 01

Date Approved: Dec 2024



#### Loads description: Site plant - Compactor plate



### Slinging methodology:

- I. Attach single leg chain sling to hook block of the crane.
- II. Attach hook of chain sling to the integral lifting point of the compactor plate

Lift Category:	Basic			
Dimensions of load:	Various dimensions: Typically, 600 mm [w] x 1264 mm [h] x 809 mm[l] overall length with handle up			
Weight of Load	Typically, 200kg for dimensions give	en		
Lifting accessories	From hook block > WLL x Mode Factor Resulting SWL Single leg chain sling WLL 1.4 t @			
used with weights of accessories:	25 kg  Gross weight inc. 10% FOS: 248 kg [ru]	Single leg chain sling as per designed use  1.4 t over accessories stated		
Alternative methodology:	Single leg of a multileg chain sling of sufficient WLL can be used with the unused legs hung back to the master ring.			
Safe lifting considerations:	<ol> <li>Check compactor to ensure that all components are secure.</li> <li>Ensure centre of gravity prior to lifting.</li> <li>Check integral lifting eye for deformities.</li> <li>Ensure the compactor is free from oil and fuel leaks.</li> <li>Check the 'plate' for any loose stones or mud that could fall when lifted.</li> <li>Ensure the compactor is turned off.</li> </ol>			

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 94 of 118

Document No.: Document Rev: Date Approved:



#### Loads description: Site plant – Drum Roller



### Slinging methodology:

- I. Attach single leg chain sling to hook block of the crane.
- II. Attach hook of chain sling to the integral lifting point of the compactor plate

Lift Category:	Basic				
Dimensions of load:	Various dimensions: Typically, 770 mm [w] x 1220 mm [h] x 870 mm [l]				
Weight of Load	Typically, 266 kg for dimensions given	ven			
Lifting accessories	From hook block > Single leg chain sling WLL 1.4 t @	WLL X MODE FACTOR RESULTING SWL			
used with weights of accessories:	25kg  Gross weight inc. 10% FOS: 321 kg [ru]	Single leg chain sling as per designed use	1.4 t over accessories stated		
Alternative methodology:	Single leg of a multileg chain sling of sufficient WLL can be used with the unused legs hung back to the master ring.				
Safe lifting considerations:	<ol> <li>Check roller structure to ensure that all components are secure.</li> <li>Ensure centre of gravity prior to lifting.</li> <li>Check integral lifting eye for deformities.</li> <li>Ensure the roller is free from oil and fuel leaks.</li> <li>Check the 'rollers' for any loose stones or mud that could fall when lifted.</li> <li>Ensure the roller is turned off.</li> </ol>				

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 95 of 118

Document No.: Document Rev: Date Approved:



#### Loads description: Site plant - Power trowel [float]



### Slinging methodology:

- I. Attach single leg chain sling to hook block of the crane.
- II. Attach hook of chain sling to the integral lifting point of the power trowel

Please note:
Ensure the hook of the chain sling fits the lifting aperture. If required a bow shackle of a suitable WLL can be used to ensure integrity of attachment



Lift Category:	Basic					
Dimensions of load:	Various dimensions: Typically,mm [d] xmm [h] xmm [l]					
Weight of Load	Typically,kg for dimensions	given				
Lifting accessories	From hook block > WLL x Mode Factor Resulting SWL Single leg chain sling WLL 1.4 t					
used with weights of accessories:	@ 25 kg  Gross weight inc. 10% FOS:kg / t [ru]	Single leg chain sling as per designed use	1.4 t over accessories stated			
Alternative methodology:	Single leg of a multileg chain sling of sufficient WLL can be used with the unused legs hung back to the master ring.					
	Please note: Some power trowels have multi-lifting eyes around the circumference of the blade housing framework; therefore, a multi-leg chain sling must be employed of the sufficient WLL. Consult the operator's manual for correct configuration of the lifting arrangement. Any unused chains are to be hung back to the master ring					
Safe lifting considerations:	<ol> <li>Check power trowel structure to ensure that all components are secure.</li> <li>Check integral lifting eye for deformities.</li> <li>Ensure the power trowel is free from oil and fuel leaks.</li> <li>Check the 'blades' for any loose stones or mud that could fall when lifted.</li> </ol>					
	V. Ensure the power trowel is turned off					

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 96 of 118 Document No.: Document Rev: Date Approved:



#### Load description: Steel beams - Girders, H section, I section, U beams, Lintels

### Special note:



Structural steelwork and fabricated steel assemblies shall have designed lifting points or a method for making a positive connection to a removable lifting bracket.

### Slinging methodology:

- 4 leg chain slings will be attached to hook block of the crane. Only 2 legs required so any unused chains will be hung back to the master ring.
- II. Attach hooks of chain sling to the integral lifting eyes of the beam.

#### Please note:

Ensure the hook of the chain sling fits the integral lifting eye.

If required bow shackles of a suitable WLL with mode factors considered can be utilised to ensure integrity of attachment.



Lift Category:	Basic				
Dimensions of load:	Various dimensions:mm [h] xmm [l] xmm [w]				
Weight of Load	_kg / t for dimensions given	_kg / t for dimensions given			
Lifting accessories	From hook block:	WLL x Mode Factor	Resulting SWL		
used with weights of	4 Leg chain slings WLL 8.4 t @ 103kg	4 leg chain slings with 2 legs in use - WLL of one leg	4.41 t over all accessories		
accessories:	Gross weight inc. 10% FOS: _kg	multiplied by 1.4 = 4.41 t	stated		
Alternative methodology:	Other attachment accessories can also be used to provide a 'positive' attachment, much like the integral lifting points, through predrilled holes in the structure of the beams - See examples opposite.				
	When lifting with these accessories ensure they are used as per manufacturers specification and instructions.				
	Webbing slings can be used around beams in a double wrap 'choke' configuration.				
	Ensure wear sleeves are used to protects the webbing slings from any sharp or burred edges.				
	If size of hook block allows, and the EWL of the slings is sufficient enough to allo excluded angle, then the webbing c	0 0	n a 0 to 45 deg.		

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 97 of 118 Document No.: Document Rev: Date Approved:



XXXX\_XXXX\_XXXX

01

Dec 2024

Document No.:

Document Rev:

Date Approved:

Load description:	Load description: Steel beams - Girders, H section, I section, U beams, Lintels			
Alternative methodology: contd.:	Slings to be placed to suit a level load.  DO NOT OVERCROWD THE BLOCK			
Safe lifting considerations:	<ul> <li>I. With direct attachment of the chain sling, ensure the chain sling attaching to the top of the beam is of sufficient length to allow for the chain to be within a 0 to 45 deg. excluded angle.</li> <li>II. A temporary works check on the attachment points to have been completed prior to lifting.</li> <li>III. Tagline[s] to be used to allow configuration of beam to be controlled from initial raising of the beam to final lowering (installation).</li> </ul>			
Additional information:	initial raising of the beam to final lowering/installation.  Reference weights: If beams are not marked with the known weight, then always check with manufacturer and design drawings for anticipated weights of beams supplied.  Special note: Always check with design drawings that any welds, or additional bolted assemblies etc. are included in the weight			



### Loads description: Loading platform



Image above is representational only of a 4 point lift typical of methodology for a loading platform.

### Slinging methodology:

- I. Attach 4 leg chain sling to hook block of the crane.
- II. If required shorten chain slings to suit methodology of install [see operators manual or safe user guide for recommended length of chains]
- III. Attach hooks of chain sling to the integral lifting points situated to the structure of the platform.

#### Please note:

See manufacturer's specification sheet, operating manual, or safe user guide to identify the lifting points recommend for each model of loading platform being lifted.


Lift Category:	Intermediate [as minimum]	Complex [dependant on localised parameters and hazards]	
Dimensions of load:		110 mm [w] x 1000 mm [h] x 9000 mm [l] for ck manufacturer's specification for 'other' model	
Weight of Load	Typically, 3 t for dimensions given		
Lifting accessories	From hook block > Single leg chain sling WLL 8.4.t@	WLL x Mode Factor Resulting SWL	
used with weights of accessories:	103kg  Gross weight inc. 10% FOS: 3.414 t [ru]	4 leg chain sling as per designed use 8.4 t over accessories stated	
Alternative methodology:	See manufacturer's literature to configure the accessories to suit loading platform. Where required bow shackles may need to be utilised to enable a correct attachment of the hooks of the chain sling to lifting points of the loading platform. Ensure they are of sufficient WLL with mode factors considered.		
Safe lifting considerations :  Safe lifting considerations contd.:	<ul> <li>I. A specific risk assessment and method statement must be authored to suit the lifting of the Loading platform from preparation of the arrangement through to final install and release of accessories.</li> <li>II. Prior to lifting ensure checks are made to the loading platform to ensure integrity of attachment of all components See list and graphic on next page for details.</li> <li>III. Attach tagline to aid control of configuration of platform through the initial raising process</li> </ul>		

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 99 of 118 Document No.: Document Rev: Date Approved:



#### Loads description: Loading platform

See below graphic for typical checks to be made to Loading platforms. The checks are inclusive of 'Roller' models of Loading platforms.



#### Please note:

This is not an exhaustive list and manufacturers checklists are to be obtained, and the checks contained within followed.

- 1. Check base prop & leg assembly [if applicable].
- 2. Check base bar assembly.
- 3. Check that prop legs are plumb.
- 4. Check prop head to spreader beam fixings or prop 'flat' head to slab [if applicable].
- 5. Check screw jacks are tight and to the correct height.
- 6. Check top bar assembly
- 7. Check handrail assembly.
- 8. Check all deck plates to inner beam bolt plates are intact and present [if applicable].
- 9. Check the condition of the side structure including all fixing bolts and pins.
- 10. Check the condition of the doors, and again ensure all fixing bolts and pins are present.
- 11. Check condition of lifting eyes and any fixed 'Bow' shackles [if applicable]
- 12. Check stoppers and bolts for deformation or signs of fatigue.
- 13. Check rolling action [Roller platforms only]
- 14. Check Deck locking bolt action [Roller platforms only]

#### Special note:

Check for any specific requirements when lifting the deck whilst it is extended, sometimes a balancing weight may be required to be fixed to the deck prior to lifting.

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 100 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01

oved: Dec 2024



### Loads description: Carrying of personnel - Use of Suspended Personnel Carrier

#### Special note for the following schedule:

All crane manufacturer manuals forbid the use of cranes for lifting people as a failure in the hoist rope means the hook and load will fall and should be avoided.

However, if the lifting of personnel is unavoidable, then a stand-alone lift plan must be in place for the operation as per BS 7121-1:2016 which specifies that the lifting of persons should be classified as a 'Complex lift', therefore it is essential that each lifting operation involving the lifting of persons is individually planned, taking into account all hazards identified by the risk assessment.

As per BS7121- Part 1: Section 4: 4.3.2.4 The appointed person responsible for the lifting operation should be present on the project

The inclusion of this lifting operation in a schedule format is to provide a brief overview of the safe lifting considerations for this lifting operation.

The schedule format can be used in the stand-alone lift plan mentioned previously.

#### References:

#### External:

- LOLER 1998 Lifting Operations and Lifting Equipment Regulations (LOLER) 1998
- TCIG TIN 040 Lifting of Persons with Tower Cranes
- Working at height on Mobile Cranes
- BS7121 Part 1: 20.1 Raising or lowering of personnel
- BS EN 14502-1:2010 Cranes. Equipment for the lifting of persons Suspended baskets
- The Work at Height Regulations 2005
- HSE Work at Height

Process Owner: Head of Lifting
Approved By: C. Hook
Page: Page 101 of 118

Document No.: XXXX\_XXXXX Document Rev: 01

Date Approved: Dec 2024



### Loads description: Carrying of personnel - Use of Suspended Personnel Carrier

#### User note:

The following methodology is for a 'closed' Suspended Personnel Carrier – The schedule, if used, should be adjusted to suit 'open' Suspended Personnel Carrier operations.




### <u>Slinging methodology:-Integral chain/wire sling</u>

- I. Attach master ring of integral chain sling to the hook block of the crane.
- II. Once personnel have entered the carrier, close access/egress 'gate' and ensure integrity of closure.

#### Please note:

Ensure the attachment accessories are of such a length, that when suspended from the hook of the crane, the vertical distance between the floor of the carrier and the crane hook is  $\geq 3$  m



Lift Category:	Complex (requires a stand-alone lift plan – see note on previous page)				
Dimensions of load:	Various dimensions: Typically: 700 mm [w] x 2210 mm [h] x 1450 mm [l] [for a 2 person access cage]				
Weight of Load	Typically, 640 kg for a 2 person car	rier lifting at capacity inc. weight	of carrier.		
Lifting accessories used	From hook block > WLL x Mode Factor Resulting SWI				
with weights of accessories:	Suspended personnel carriers have integral chain slings attached. Weight of chains are included in the self-weight of the carrier.  Gross weight inc. 50% FOS: [ru] @ wcs for use of externally supplied chains [for a 2 person carrier]	Integral chains as per designed use for carrier used at WLL.	_ kg over accessories stated [limited to WLL of the carrier utilised]		
Safe lifting considerations:	Before work taking place ensure a at the planning stage:	'Hierarchy of Control' has been	evaluated & applied		

Process Owner:Head of LiftingDocument No.:Approved By:C. HookDocument Rev:Page:Page 102 of 118Date Approved:

Document No.: XXXX\_XXXX\_XXXX
Document Rev: 01
Date Approved: Dec 2024



#### Loads description: Carrying of personnel - Use of Suspended Personnel Carrier

## Safe lifting considerations contd.:

- Ensure the possibility of MEWPs has been thoroughly investigated and deemed to be impractical
- Plan the works so that temporary or building structures can be utilized rather than resorting to access cage duties.

If the suspended personnel carrier is the only way to provide access to the work face, then:

Ensure the crane is fit for use - Refer to BS7121 – Part 1:2016 & TCIG TIN 040 for detailed crane requirements when lifting personnel.

https://www.cpa.uk.net/downloads/195/CPA-TCIG-TIN-040-Issue-A-140402.pdf

Check the weather forecast - Suspended personnel carrier duties are restricted in wind speeds over 7m/s

Do not attempt to perform the work in a 'window' between gusts - plan the works where there is a period of anticipated low wind speeds.

The crane operator must be competent & comfortable with performing the lifting operation.

No lone working. A minimum of 2no. operatives to be always present in the carrier, of which one must be a competent slinger signaller.

Do not enter or exit the carrier unless at ground level and cage is stationary and stable.

Prior to lifting ensure:

- All tools are tethered to relevant personnel or handrails.
- That all operatives are wearing a harness and restraint lanyard.
- That operatives attach their lanyard from the harness to an identified anchorage point.

Checks to be made to the attachment point to ascertain it is fit for use

[Seek manufacturer's guidance if the information isn't readily available from official literature.]

 Ensure the length of the lanyard restricts access from the carrier.



Limit the amount of time spent utilising the suspended personnel carrier.

#### Keep the work short-term.

There must always be a slinger-signaller in the carrier with a radio that has a dedicated crane channel for communication with the crane operator, lift supervisor & appointed person.

In case of radio failure or the battery running out, make sure that you have the operative's phone numbers -Ensure that phones are adequately charged.

Ensure that communications to the crane operator are performed on a licensed Ofcom registered radio frequency channel.

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 103 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01



### Loads description: Carrying of personnel - Use of Suspended Personnel Carrier

Hold point:

Only use dedicated crane communication radios.

Safe lifting considerations contd.:

Radio checks to be performed prior to entering the carrier.

Slinger - signaller to be issued with a fully charged 'spare' battery

Ensure that there are spare batteries put aside solely for suspended personnel carrier operations if anticipated.

Slinger signaller and crane operator to have a full understanding of the English language so that there is no ambiguity when instructions are given.

Slinger signaller and other operatives to have adequately charged mobile phones as a backup in case of catastrophic communication failure.

Hold point:

All operatives involved to have each other's mobile number, inclusive of the lift supervisor and appointed person

Personnel in the carrier must be:

- Harness trained in the use of the harness being used.
- Have undergone working at height training
- Of a calm and pragmatic disposition.
- Physically fit.

### Whilst in the cage do not:

- Lean from the carrier structure.
- Stand on the guardrails or place materials on platforms, guardrails.
- Use boxes, steps etc. to gain extra height.
- Behave in a way that will cause 'rocking' movement of the carrier.

A suitably risk assessed rescue plan to be in place prior to the lifting operation taking place which **must** consider [non-exhaustive]:

• Operative's requirements if they find themselves in the carrier for some time

due to mechanical failure of the crane

 Placement of a safety rope in the carrier of sufficient length so that food, drink, extra clothing, and rescue equipment can be attached for 'pulling up' into the carrier structure.

The rope should be contained within suitable containment i.e. bag etc. and secured to an identified 'storage' point within the confines of the carrier structure that does not hinder the safe execution of the works being performed

Special note:

Do not load the suspended personnel carrier with rescue items unless there is sufficient room.

Process Owner: Head of Lifting
Approved By: C. Hook
Page: Page 104 of 118

Document No.: XXXX\_XXXX\_XXXX Document Rev: 01

Date Approved: Dec 2024



#### Loads description: Carrying of personnel - Use of Suspended Personnel Carrier

This can cause its own hazards while in the confines of the carrier.

## Safe lifting considerations contd.:

• Gauge how long the operatives will be in the carrier - Have conversations with the crane supplier for maximum 'response times' that are anticipated for service/repair engineers' attendance.

Ensure the master ring of the integral chain/wire rope slings, correctly in the bowl of the crane hook

Before attachment of the carrier, ensure that the gate/door to the carrier is secure and works as anticipated & that the integral chains are fit for use and configured correctly.

### Hold Point:

Any door or gate for entering or leaving a carrier should always open inwards and must have an automatic catch to prevent it from being opened inadvertently



Check attachment points for the chain/wire rope slings for any signs of deformation that could impede the safe use of the suspended personnel carrier.

#### Hold point

Has the carrier undergone painting recently that could hide deformities?

Check inside the structure of the carrier for any loose materials left over from previous use - If found remove.


Check for openings in the carrier that could enable materials or tools to fall from the structure.

Perform a test lift of the carrier for stability & lifting level

Check the underside of the structure to ensure that there isn't anything adhered/attached to the bottom that could fall off or become dislodged when travelling across the project.

While performing the 'test' lift, check the weight of the carrier to ensure it is not overloaded.

Remember the attachment of tagline(s?) to the structure of the carrier to assist in the control and configuration from the initial raising, through to the final lowering of the carrier If practicable.



No standing under the carrier when landing. - Identify a 'Safe Space' to stand when landing the load.

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 105 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX
01



### Loads description: Carrying of personnel - Use of Suspended Personnel Carrier


Ensure there are full physical exclusion and restricted zones set up directly below the anticipated area of works

## Safe lifting considerations contd.:

Hold point:

When setting up exclusion zones, ensure consideration has been given for an allowance with the zonal parameters for objects falling from within the confines of the carrier attending to and allowing for a worst case scenario trajectory.

See example exclusion set up below:





#### Loads description: MEWPs



#### Please note:

Images are representational only - see manufacturer's literature for lifting arrangement to be used on each model.

### Slinging methodology:

- I. 4 leg chain slings will be attached to hook block of the crane.
- II. Attach hooks of the 4 leg chain sling directly to the identified lifting points of the MEWP

#### Please note:

- a. A specific wind speed assessment is required when considering the limiting wind speed when lifting such machines.
- b. Bow shackles may be required between the hooks of the chain sling and the identified lifting point on the MEWP to allow a safe attachment.
- c. Chain slings may require shortening to suit a level load

Lift Category:	Intermediate [as minimum] Complex [dependant on localised parameters and hazards]			
Dimensions of load:	Various dimensions and weights over different models See manufacturer's operations manual or contact supplier for information			
Weight of Load				
Lifting accessories	From hook block > 4 Leg chain slings WLL 8.4 t @	W	LL x Mode Factor	Resulting SWL
used with weights of	103kg	4 leg	g chain slings as per design use	
accessories:	_no. Bow shackles WLL _t@ _kg ea.	no. b	oow shackles used as	_t over accessories stated
	Gross weight inc. 10% FOS: _t [ru]	set = WLL of one multiplied by = _ kg / t		
Alternative methodology:	Various methodologies use over varying models. – See manufacturer's operating manuals for guidance on how to lift the MEWP. If the guidance is unclear, then contact the supplying company or manufacturer for definitive information.			
	Example of manufacturer's guidance on lifting arrangement:    The Column   Second Printing   Coperative Manufacturer   Cop			

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 107 of 118 Document No.: Document Rev: XXXX\_XXXX\_XXXX
01

Date Approved:



#### Loads description: MEWPs

### Safe lifting considerations:

- I. Ensure the machine is switched off prior to lifting
- II. Verify that the identified lifting points are free from deformities that could affect the integrity of the attachment of the accessories.
- III. Check structure of the MEWP for any signs of hydraulic leaks.
- IV. Check that the accessories passing near or over any component part or structure of the MEWP that, once weight has been taken, will not subject the MEWP to crushing or undue pressure.

#### Please note:

Handrails etc. are easily bent meaning the machine will have to be quarantined until any damage repaired.

- V. Ensure that the platform and structure of the MEWP is free from loose materials and tools. If found, remove.
- VI. During the test lift check the underside and tyres/wheels of the MEWP for any mud etc. that may have adhered.

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 108 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01



#### Loads description: Toolbox



### Slinging methodology:

- 4 leg chain slings will be attached to hook block of the crane. Only 2 legs required so any unused chains will be hung back to the master ring.
- II. Attach webbing slings min WLL 2 t through the fork points of the toolbox and around the structure of the box in a single wrap captured 'choke' configuration.

Please note:

If box doesn't have fork points, then the slings should be double wrapped.

Lift Category:		Basic	
Dimensions of load:	Various dimensions: Typically: 550 mm [w] x 590 mm [h] x 1186 mm [l]		
Weight of Load	Typically, 75kg empty  Please note: Typically, toolboxes do not have a WLL.  Max. allowable weight on SRM projects for lifted toolboxes will be 1t unless otherwise stated in manufacturer's literature		
Lifting accessories	From hook block > 4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor	Resulting SWL
used with	103kg	4 leg chain slings with 2 legs	2.24t over accessories stated
weights of accessories:	Webbing slings WLL 2 t Min 6m (l) [for single wrap] & 8m (l) for [the	in use - WLL of one leg multiplied by 1.4 = 4.41 t 2 webbing slings used a set in a choke configuration =	
	double wrap]. @ 10kg		
	Gross weight inc. 10% FOS: 1.23 t [ru] for fully laden toolbox with SRM permissible weight	[WLL of one sling multiplied by 1.4] x .8 = 2.24 t	
Alternative methodology:	Chain slings can be employed in the same configuration stated for the webbing slings.  Ensure when sling with chain slings that the chains, when tightened, do not affect the integrity of the box i.e., crush or deform the structure		
	If size of hook block allows, then the webbing slings can be directly attached.		
	DO NOT OVERCROWD THE	вьоск	

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 109 of 118 Document No.: Document Rev: Date Approved:



Loads description: Toolbox				
Safe lifting considerations:	I.	During test lift, check the underside of the toolbox for any materials, mud etc, that could have adhered itself to the bottom of the box structure. If applicable check the fork points for the same.		
	II.	Check structure of box for creases or holes in base and sides that could affect the safe lifting.		
Safe lifting	III.	Check load for level.		
considerations contd.:	IV.	Ensure that any materials, tools etc. are secured so that any movement in the box doesn't affect the CoG through the lift. If there is doubt, then remove prior to lifting.		

Process Owner: Head of Lifting
Approved By: C. Hook
Page: Page 110 of 118

Document No.:XXXX\_XXXX\_XXXXDocument Rev:01Date Approved:Dec 2024



### Loads description: Transformer box up to 20kva



### Slinging methodology:

- 4 leg chain slings will be attached to hook block of the crane. Only 2 legs required so any unused chains will be hung back to the master ring.
- II. Attach 2no. Webbing sings min WLL 2 t around the transformer box in a double wrap 'choke configuration

#### Please note:

For smaller transformer boxes a single webbing sling can be used in a double wrap configuration around the box as long as it is fed through the carrying handle situated to top of the box to form a captured 'choke'

Lift Category:	Basic			
Dimensions of load:	Various dimensions: Typically, 640 mm [w] x 950 mm [h] x 1500 mm [l]			
Weight of Load	Typically, 300 kg for dimensions given			
Lifting accessories used with	From hook block > 4 Leg chain slings WLL 8.4 t @ 103kg	WLL x Mode Factor	Resulting SWL	
weights of accessories:	Webbing slings WLL 2 t Min 4m (l)	4 leg chain slings with 2 legs in use - WLL of one leg		
	@ 10kg  Gross weight inc. 10% FOS: 455 kg [ru]	multiplied by 1.4 = 4.41 t  2 webbing slings used a set in a choke configuration = [WLL of one sling multiplied by 1.4] x .8 = 2.24 t	2.24 t over accessories stated	
Alternative methodology:	Chain slings can be used in the same configurations around the boxes as the webbing slings shown.  If size of hook block allows, then the webbing slings can be directly attached.  DO NOT OVERCROWD THE BLOCK			
Safe lifting considerations:	<ol> <li>Check structure of box for any lose tools etc. that could fall when lifting.</li> <li>Check any compartments for loose tools or equipment that may have been placed inside.</li> <li>Check all doors [if applicable] are locked/secured prior to lifting.</li> <li>Ensure that any leads/cable have been disconnected.</li> <li>Protect the webbing sings from any burrs or sharp edges on the box structure by using wear sleeves at the pinch points</li> <li>Check the data plate on the side of the box for weight.</li> </ol> DO NOT LIFT FROM THE MANUAL HANDLES			

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 111 of 118 Document No.:
Document Rev:

Date Approved:



#### Loads description: Pedestrian barriers



### Slinging methodology:

- I. 4 leg chain slings will be attached to hook block of the crane. Only 2 legs required so any unused chains will be hung back to the master ring.
- II. Attach 2no. Webbing sings min WLL 2 t through the vertical barrier 'stack' in a 'choke configuration.

Lift Category:	Basic			
Dimensions of load:	Various dimensions: Typically, 100 mm [w] x 1100 mm [h] x 2300 mm [l]			
Weight of Load	Typically, 400 kg for vertical 'stack' of 25 @ 16 kg ea. barrier			
Lifting accessories	From hook block > 4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor	Resulting SWL	
used with weights of	103kg	4 leg chain slings with 2 legs in use - WLL of one leg multiplied by 1.4 = 4.41 t	2.24 t over accessories stated	
accessories:	Webbing slings WLL 2 t Min 4m (l) @ 10 kg			
	Gross weight inc. 10% FOS: 565 kg [ru]	2 webbing slings used a set in a choke configuration = [WLL of one sling multiplied by 1.4] x .8 = 2.24 t		
Alternative methodology:	Chain slings can be used in the same configuration as the webbing slings.			
	If size of hook block allows, then the webbing slings can be directly attached.			
	DO NOT OVERCROWD THE BLOCK			
Safe lifting considerations:	I. Sling load to allow a safe landing.			
	II. Check the legs of the panels for any mud etc. that could be in the leg from where it was stored or used.			

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 112 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01

red: Dec 2024



#### Loads description: Heras fence panels - Stillage & Loose bundles



### Slinging methodology: - In stillage

- 4 leg chain slings will be attached to hook block of the crane. Only 2 legs required so any unused chains will be hung back to the master ring.
- II. Attach 2no. Webbing sings min WLL 2 t around the stillage in a double wrap 'choke' configuration.

### Slinging methodology: - Loose

- 4 leg chain slings will be attached to hook block of the crane. Only 2 legs required so any unused chains will be hung back to the master ring.
- II. Attach 2no. Webbing sings min WLL 2 t around the panel stack in a double wrap 'choke' configuration.

Lift Category:	Basic			
Dimensions of load:	Various dimensions but typically: 2000mm [w] x 1550mm [h] x 3500mm [l] [in stillage]			
Weight of Load	Typically, 624kg [30 panels in stillage] & 420kg [30 panels loose]			
Lifting accessories	From hook block > 4 Leg chain slings WLL 8.4 t @	WLL x Mode Factor	Resulting SWL	
used with weights of	103kg	4 leg chain slings with 2 legs	2.24t over accessories stated	
accessories:	Webbing slings WLL 2te. Min 10m (l) @ 15 kg	in use - WLL of one leg multiplied by 1.4 = 4.41 t		
	Gross weight inc. 10% FOS: 817 kg [ru] wcs in stillage	2 webbing slings used a set in a choke configuration = [WLL of one sling multiplied by 1.4] x .8 = 2.24 t		
Alternative methodology:	If size of hook block allows, then the webbing slings can be directly attached.			
<b>87</b>	DO NOT OVERCROWD THE BLOCK			
Safe lifting considerations:	I. Protect the webbing sings from any burrs or sharp edges on stillage and panel structures by using wear sleeves at the pinch points.			
	II. Check the feet of the stillage for any mud etc. that could be in the leg from where it was stored.			
	<ul> <li>III. Ensure the integrity of the load by using a ratchet strap or securing banding around the load.</li> <li>IV. Ensure when landing loose panels that timbers/spacers are of sufficient size to allow safe removal of accessories.</li> </ul>			

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 113 of 118 Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX
01

pproved: Dec 2024



#### Loads description: Excavator buckets



### Slinging methodology:

- 4 leg chain slings will be attached to hook block of the crane. Only 2 legs required so any unused chains will be hung back to the master ring.
- II. Attach the chain slings around the 'pin' of the excavator bucket in a single wrap, captured choke configuration.

#### Please note:

If smaller buckets do not allow room for 2 chains, then a single chain can be attached in the same configuration.

Lift Category:	Basic			
Dimensions of load:	Various dimensions: 1200mm [l] x 973mm [l] x 1560mm [d] [for a 22t excavator digging bucket]			
Weight of Load	Typically, 1.629 t For given dimensi	ons		
Lifting accessories used with weights of accessories:	From hook block > 4 Leg chain slings WLL 8.4 t @ 103kg  Gross weight inc. 10% FOS: 1.906 t [ru]	WLL x Mode Factor  4 leg chain slings with 2 legs in use - WLL of one leg multiplied by 1.4 = 4.41 t	Resulting SWL  4.41 t over accessories stated	
Alternative methodology:	Multiple buckets can be slung together.  When lifting multiple buckets, consider the safe landing of the buckets.  To ensure a safe configuration of landing either sling the buckets in a 'stack, where the buckets are arranged to fit inside each other or sling the buckets 'back-to-back'.  In each methodology ensure the chains slings capture all the pins on each bucket.			
Safe lifting considerations:	<ul> <li>I. Check integrity of the 'pin' prior to lifting. Check for splits or cracks that could affect the integrity of the attachment</li> <li>II. When slinging smaller buckets, do not sling with direct attachment to the 'pin'.  The bucket could slide against the hook while travelling and impose side loadings on the hook that may not fail at the time of lift but will affect long term use of the chain.</li> <li>III. If you can't choke a chain sling around the 'pin', then utilise a webbing sling of sufficient WLL in 'choke configuration.</li> <li>IV. Check bucket interior for mud, earth etc. that could fall when lifted.</li> </ul>			

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 114 of 118

Document No.: Document Rev: Date Approved: XXXX\_XXXX\_XXXX 01



#### Loads description: Timber 'Ekki' mats



### Slinging methodology:

- 4 leg chain slings will be attached to hook block of the crane. Only 2 legs required (see note below) so any unused chains will be hung back to the master ring.
- II. Attach the hooks of the chain slings to the lifting points.

#### Please note:

Some timber mats will arrive with 4 'notches' for the attachment points, when lifting these mats ALL lifting points must be used.

Lift Category:	Basic			
Dimensions of load:	Various dimensions (but for purposes of schedule) : 5000 mm [l] x 1000 mm [w] x 150 mm [h]			
Weight of Load	Typically, .981 tonnes for dimensions given of a hardwood excavator mat			
Lifting accessories used with weights of accessories:	From hook block > 4 Leg chain slings WLL 8.4 t @ 103kg  Gross weight inc. 10% FOS: 1.193 t [ru]	WLL x Mode Factor  4 leg chain slings with 2 legs in use - WLL of one leg multiplied by 1.4 = 4.41 t	A.41 t over accessories stated	
Alternative methodology:	If lifting across project, then the stamats should be treated as any other pack/bundle and be slung in a doul configuration utilising webbing slin sufficient SWL after the mode factor considered. See schedule titled 'Tir Bundles' for details on methodolog lifting considerations.  It is also acceptable to lift multiple together by feeding the hook of a clot between the structure of the mats a attachment points and hooking one bottom mat attachment point. Be attachment points and spacing of aperture may for this methodology can be problemated in and spacing of aperture may for this methodology.  Best practice for this methodology use a fabric sling in a captured chol configuration  Hold point:  Always check with the manufactured acceptable and within the capabilities.	ck or pack of or timber pole wrap pigs of rs have been pigs and safe pigs and the to the piware that tic as size of not be suited pieces.  Tor supplier of the mats that this		

Process Owner: Head of Lifting
Approved By: C. Hook
Page: Page 115 of 118

Document No.: XXXX\_XXXX\_XXXX
Document Rev: 01
Date Approved: Dec 2024



### Loads description: Timber 'Ekki' mats

### Alternative methodology:

Do not lift the stack or pack of mats with the chain sling fed on the outside of the attachment points as:


- The higher layers [above the bottom mat] aren't captured by the accessories
- When attaching the hook of the chain sling to the lifting point pressure of the lift could be put on the hook that the hook isn't designed for.
- The load is also at considerable risk of rotating as the centre of gravity of the load is above the load attachment point.



When using a chain sling or webbing sling fed through the attachment aperture for multi mat stacks, this should be a low-level lift for placing only - Only ever lift a maximum of 4no. mats in this configuration.

### Safe lifting considerations:

- I. Check integrity of the attachment point prior to lifting Check for splits or cracks around the immediate area that could affect the integrity of the attachment
- II. Examine the structure of the mat, again for any cracks, splits, deterioration that could be problematic when lifting and bring into doubt the integrity of the load
- III. Ensure the underside of the mat is free from adhered materials that could fall during travel of the load.
- IV. If required, use webbing sling wear sleeves (or similar) where the mats have sharp edges.
- V. When slinging in packs ensure securing banding is used around the load to negate any spread of the load when landed.
- VI. Always ensure that the hook of the chain sling can move freely within the confines of the attachment point. Don't force the hook into the aperture
- VII. After attachment of hook, check the attachment point sits in the bowl of the hook correctly.





Process Owner: Approved By: Page: Head of Lifting C. Hook Page 116 of 118 Document No.: Document Rev: Date Approved:



Loads description: Template					
			Slinging methodology I. II.	<u>:</u>	
Lift Category:	Basic		Intermediate		Complex
Dimensions of load:					
Weight of Load					
Lifting accessories	From hook block >		WLL x Mode Fact	or	Resulting SWL
used with weights of accessories:	Gross weight inc. 10% FOS: [ru]	t			over accessories stated
Alternative methodology:	-		<u> </u>		
Safe lifting considerations:					

Process Owner: Approved By: Page: Head of Lifting C. Hook Page 117 of 118

Document No.: Document Rev: Date Approved:



# Proudly building Britain's future heritage

Sir Robert McAlpine Ltd Eaton Court | Maylands Avenue | Hemel Hempstead Hertfordshire | HP2 7TR

+44 (0) 333 566 3444 information@srm.com

www.srm.com